

4-020043

1-17

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,734 ⁻⁰⁰⁻⁰⁰

NW SE NW /4 SEC. 15, 06 S, 24 W
3630 feet from S section line
3630 feet from E section line

Operator license# 04767

Lease: Moore Estate Well # 1

Operator: Ritchie Exploration, Inc.

County: Graham

125.61

Address: 125 N. Market
Suite 1000
Wichita, Kansas 67601

Well total depth 3865 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 297 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Murfin Drilling Co. License# 30606

Address: 250 N Water, Suite 300, Wichita KS 67202

Company to plug at: Hour: PM Day: 16 Month: January Year: 1994

Plugging proposal received from: Lloyd Dellett

Company: Murfin Drilling Co. Phone: 316-267-3241

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2125 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1310 feet with 100 sacks

3rd plug @ 350 feet with 40 sacks

4th plug @ 40 feet with 10 sacks

Plugging Proposal Received by: Ken Kuhn

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 1:30am, Day: 17, Month: January, Year: 1994

Actual plugging report: Hole reported plugged as above.

Order 215 sx 60/40 pozmix w/ 6% gel and 2.2 sx celloflake or floccel.

RECEIVED
STATE CORPORATION COMMISSION
1-24-94
JAN 24 1994

Remarks: Allied Cementing performed the cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: 2460 GL

I did did not [X] observe the plugging. Ken Kuhn
(agent)

INVOICED
DATE 1-28-94
INV. NO. 39828

HO. Form CP-2/3

CONSERVATION DIVISION
Wichita, Kansas