

4-071170

API Number: 15-065-22,767

00-00

3-13

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

S2 SW SE /4 SEC. 32, 06 S, 23 W
330 feet from S section line
1980 feet from E section line

Operator license# 4197

Lease: Walters Well # 1-32

Operator: Dunne Oil Company

County: Graham

Address: 100 S. Main - Suite #410
Wichita, Kansas 67202
Stephen W. Dunne

Well total depth 3965 ^{128.86} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 304 feet

Aband. oil well___, Gas well___, Input well___, SWD___, D & A X

Plugging contractor: Murfin Drilling Company, Inc. License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: A.M. Day: 13 Month: March Year: 1996

Plugging proposal received from: Keith VanPelt

Company: Murfin Drilling Company, Inc. Phone: 316-267-3448

Were: 8 5/8" - 304' S.P. cwc. w/225 sxs 60/40 pozmix - 2% gel - 3% c.c. By Allied Cement. Elv. 2495' - Anhy. 2176' - K.C. Well. No circulation problems. Mud condition 50 vis. - 9.2 wt. - 8.8 water loss - 600 ppm cl at 3912'. Proposal 190 sxs 60/40 pozmix - 6% gel and 1/4# flocele per sack - spot and displace all cement through drill pipe - heavy mud between all plugs. 25 sxs at 2190' - 100 sxs at 1345' - 40 sxs at 350' - 10 sxs 40' - 15 sxs in rathole (circulate).

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 2:15 P.M., Day: 13, Month: March, Year: 1996

Actual plugging report: Murfin Oil ordered 190 sxs 60/40 pozmix - 6% gel and 1/4# flocele per sack. Spotted and displaced all cement through drill pipe with heavy mud between all plugs. 1st. Plug at 2190' w/25 sxs. cement. 2nd. Plug at 1345' w/100 sxs. cement. 3rd. Plug at 350' w/40 sxs. cement. 4th. Plug at 40' w/10 sxs. cement. 15 sxs in rathole (circulated).

Remarks: Cemented by Allied Cement.

Condition of casing(in hole): GOOD X BAD___ Anhy. plug: YES X NO___
Bottom plug(in place): YES___, CALC___, NO___ Dakota plug: YES X NO___
Plugged through TUBING___, CASING___ Elevation:___ GL

I did[] / did not[X] observe the plugging.

Marion J. Schmidt
(agent)
KANSAS STATE CORPORATION COMMISSION
1996 MAR 17 11:17
FORM CP-2/3
3-22-96

INVOICED

DATE MAR 26 1996

INV. NO. 45130

3-13