

4-061094

7-26

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-065-20,823-0001

SW SW SE /4 SEC. 36, 06 S, 23 W  
330 feet from S section line  
2310 feet from E section line

Operator license# 30970

Lease: Law Well # 1 OWWO

Operator: Golden Oil Company

County: Graham 124.80

Address: P.O. Box 861  
Hays, Kansas 67601

Well total depth 3840 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 253 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Paramount Casing Crews License# -

Address: 2905 Barclay - Hays, Kansas 67601

Company to plug at: Hour: 10:00 A.M. Day: 26 Month: July Year: 1997

Plugging proposal received from: Ron Geist

Company: Paramount Casing Crews Phone: 913-628-1099

Were: Order 200 sxs 60/40 posmix - 10% gel and hulls. Plug while pulling casing.  
Well tested non-commercial.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 2:30 P.M., Day: 26, Month: July, Year: 1997

Actual plugging report: 8 5/8" to 253' w/100 sxs. 4 1/2" to 3756' w/150 sxs. Well tested non-commercial. Sanded 50' above top perf and spotted 4 sxs cement with dump bailer. Cut casing loose at 2057' and pulled to 2050'. Mixed and pumped 95 sxs cement with 300# hulls. Pulled casing to 1250' and pumped 40 sxs w/100# hulls. Pulled casing to 200' and circulated cement with 40 sxs. Pulled casing with cement in cellar.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES NR NO

Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING X. Elevation: 2381 GL

I did [ ] / did not [ X ] observe the plugging.

*[Signature]*  
DK (agent)

Form CP-2/3

INVOICED

DATE AUG 07 1997

INV. NO. 48740

7-26

OCT 30 1997