

To: 6 030961
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-30-87
API NUMBER 15- 065-20,883 -00-00
2E SW
SW, SEC. 32, T 6 S, R 23 W/E

660 1320 feet from S section line
3300 3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 8461
Operator: Dyco Pet. Corp
Name & Address 7130 S. Lewis Suite 300
Tulsa, Ok. 74136

Lease Name Walters Well # 1
County Graham 129.42
Well Total Depth 3982 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 315

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton License Number _____

Address Hays, Kansas

Company to plug at: Hour: _____ PM Day: 30 Month: Sept Year: 19 87

Plugging proposal received from John

(company name) Murfin (phone) _____

were: 8 5/8" set at 315 w/200 sks. 4 1/2 set at 3982' w/200 sks. Perfs 3422' - 3919'.
Couldn't pull pipe. Ordered 250 sks 65/35 Pozmix 10% Gel 2% Dical Cement Blend.
4 sks Hulls. Halliburton Cement Co. Water Trucks.

Plugging Proposal Received by Carl Goodrow *Carl Goodrow*
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30 PM Day: 30 Month: Sept Year: 19 87

ACTUAL PLUGGING REPORT CIBP set at 3400' w/cement cap. Pipe could not be pulled.

Perforated 4 1/2" casing at 2220' w/3.5 SPF and at 1331' w/3 SPF. Squeezed 4 1/2" casing
w/150 sks Cement Blend and 3 sks Hulls. Max PSI 1000# Close in PSI 500#.

Squeeze backside (8 5/8 annulus) w/100 sks Cement Blend. Max PSI 500#. Close in PSI 200#
RECEIVED
STATE CORPORATION COMMISSION

Remarks: Plug complete.
(If additional description is necessary, use BACK of this form.)
observe this plugging.

OCT 16 1987
10-16-87
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED
DATE 10-19-87
INV. NO. 18562

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow

09-30 OCT 2 9 1987 DEC 0 3 1987