

4-071038

4-21

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,705-00-00
NE SE NE /4 SEC. 25, 06 S, 24 W
3630 feet from S section line
330 feet from E section line

Operator license# 4767

Lease Striggow-Stowell well # 1-25A

Operator: Ritchie Exploration, Inc.

County Graham

Address: 125 N. Market #1000
Wichita, Kansas 67202
Jeff Christian

Well total depth 3920 feet ^{127.40}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 257 feet

Aband. oil well __, Gas well __, Input well __, SWD __, D & A X

Plugging contractor: Murfin Drilling, Inc. License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: A.M. Day: 21 Month: April Year: 93

Plugging proposal received from: Lloyd Delleette

Company: Murfin Drilling, Inc. Phone: 316-267-4375

Were: 8 5/8" - 257' S.P. cwc. w/180 sx. 60/40 pozmix - 3% c.c. -
2% gel. By Allied Cement. Elv. 2442'. No ar buckle. Anhy. 1292'.
L.K.C. Well. No circulation problems. Mud condition 42 vis. - 9.2 wt.
9.0 water loss. Proposal 190 sx. 60/40 pozmix - 6% gel. - 3% c.c. w/1 sx
F.C. Circulate. Spot and displace all cement through drill stem with
heavy mud between all plugs. 25 sx. @ 2130' - 100 sx. w/1 sx. F.C. @
1290'- 40 sx. @ 300' - 10 sx. @ 40' - 15 sx. in rathole (circulate)

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 7:00A.M., Day: 21, Month: April, Year: 93

Actual plugging report: Murfin ordered 190 sx. 60/40 pozmix 6% gel. -
1 sx. flocele. Circulated hole. Spotted and displaced all cement
through drill pipe with heavy mud between all plugs.

1st. plug @ 2130' w/ 25 sx. cement.
2nd. plug @ 1290' w/100 sx. cement w/1 sx. F.C.
3rd. plug @ 300' w/ 40 sx. cement.
4th. plug @ 40' w/ 10 sx. cement.
15 sx. in Rathole (circulated)

Remarks: Cement by Allied Cement Company.
Condition of casing(in hole): GOOD X BAD __ Anhy. plug: YES X NO __
Bottom plug(in place): YES __, CALC __, NO __ Dakota plug: YES X, NO __
Plugged through TUBING X, CASING __. Elevation: 2442 GL

I did did not observe the plugging.

Marion J. Schmidt
(agent)

INVOICED
DATE 5-14-93
37698

RECEIVED
STATE CORPORATION COMMISSION
MAY 12 1993
CONSERVATION DIVISION
Wichita, Kansas

5-12-93