

4-061122

11-13

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-22,788 -00-00
50' W. of
NE SE SE /4 SEC. 09, 06 S, 24 W
990 feet from S section line
380 feet from E section line

Operator license# 5015

Lease: Goddard Well # 1

Operator: Hellar Drilling Company, Inc.

County: Graham 125.29

Address: 125 N. Market - #1422
Wichita, Kansas 67202

Well total depth 3855 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 304 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Pickrell Drilling License# 5123

Address: Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 13 Month: November Year: 1997

Plugging proposal received from: Doyle Folkerts

Company: Pickrell Drilling Company, Inc. Phone: -

Were: Order 190 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe. 11-20-97

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour P.M., Day: 13, Month: November, Year: 1997


Actual plugging report:

- 1st. Plug at 2160' w/25 sxs. - Anhydrite 2131' - 2167'.
- 2nd. Plug at 1350' w/100 sxs. - Dakota 1033' - 1333'.
- 3rd. Plug at 360' w/40 sxs. - Surface pipe 304'.
- 4th. Plug at 40' w/10 sxs.
- Rathole with 15 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES, CALC, NO X
Plugged through TUBING, CASING. Elevation: 2483 GL
Anhy. plug: YES X NO
Dakota plug: YES X, NO

I did [] / did not [X] observe the plugging.


DMH (agent)
Form CP-2/3

INVOICED

DATE NOV 24 1997

INV. NO. 49562