

7-26

6 031164

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,477-00-00

SW NE NW, SEC. 9, T 6 S, R 24 W/E

4290 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422

Lease Name Jamison Well # 1

Operator: Abercrombie Drilling Inc.

County Graham 125.45

Name & Address 801 Union Center

Well Total Depth 3860 feet

Wichita, Ks. 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 269

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Company Tools License Number 5422

Address Above

Company to plug at: Hour: AM Day: 26 Month: July Year: 19 88

Plugging proposal received from Harold Maley

(company name) Abercrombie (phone)

were: 8 5/8" set at 269' w/190 sks cwc. Circ. w/no less than 36 vis mud.

Balance plugs and space w/mud w/no loss or gain in fluids. Order 190 sks 60/40 Poz 6% Gel
3% Ca Cl 8 5/8" wiper plug. B. J. Titan Cement Co.

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1988

1621-88

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:30AM Day: 26 Month: July Year: 19 88

ACTUAL PLUGGING REPORT Spot plugs w/drill pipe at 2000' w/25 sks

1250' w/100 sks and Halls

320' w/40 sks

40' w/10 sks wiper plug

15 sks in rathole

Remarks: Anhy 2075' - 2108' Elev. 2457'.

(If additional description is necessary, use BACK of this form.)

(did not) observe this plugging.

DATE 10-24-88

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 22654