

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23040-00-00
Spot: E2SWNWNW Sec/Twnshp/Rge: 5-6S-21W
1030 feet from N Section Line, 500 feet from W Section Line
Lease Name: VOSS Well #: 1
County: GRAHAM Total Vertical Depth: 3820 feet

Operator License No.: 9449
Op Name: GREAT EASTERN ENERGY & DEV. CO
Address: 550 W. TEXAS STE 660
MIDLAND, TX 79702

SURF Size: 8.625 feet: 210

124¹⁵

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/15/2005 4:00 PM
Plug Co. License No.: 9292 Plug Co. Name: SCHECK, TIMOTHY DBA SCHECK OIL OPERATION
Proposal Rcvd. from: DORN Company: GREAT EASTERN ENERGY & DEV. Phone: (432) 682-1178

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE
Date/Time Plugging Completed: 04/15/2005 5:15 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 3666' w/25 sxs.
2nd. Plug at 1880' w/25 sxs.
3rd. Plug at 1153 w/100 sxs.
4th. Plug at 260' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

RECEIVED
APR 19 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED
DATE 4-19-05
INV. NO. 2005061426

Form CP-2/3

APR 18 2005