

3 022706

15-207-19495-0000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20040041

NW,SE,SW 1/4 Sec/Twp/Rge S.34-T.26S.-R.16E.

1099 feet from south section line

3647 feet from east section line

TECHNICIAN'S PLUGGING REPORT

RECEIVED

APR 04 2005

Operator License #

101

Lease/Well#

APT NO. W-5

County

WOODSON

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 1000' feet

Name &amp; FEE FUND PLUGGING

Production Pipe: Size Feet

Address

Surface Casing: 10" Size Feet 20'

AB oil well X Gas Well SWD Well/ Input Well

D &amp; A

Other well as hereinafter indicated:

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE

Lic. #

6372

Address: BOX 386, RR4, CHANUTE, KANSAS 66720

Company to plug at: Hour: 9:30A.M. Day: 29 Month: 3 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone:

620-432-2300

Were: VISIBLE ON THIS WELL WAS 10" SURFACE CASING ONLY. THE PLUGGING

PROPOSAL WAS TO DRILL OUT THE WELL AS DEEPLY AS POSSIBLE AND TO

CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All Part

TECHNICIAN

None X

Operations Completed: Hour: 12:30P.M. Day: 29 Month: 3 2005

Actual Plugging Report: A 7" BIT WAS UTILIZED TO DRILL OUT THE WELL TO 420'.

AT THAT DEPTH IRON WAS ENCOUNTERED. 1" PIPE WAS RAN INTO THE BORE TO

420'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM

THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT

WAS FILLED FROM SURFACE. 202 SACKS OF CEMENT WERE PUMPED INTO THIS

WELL.

Remarks: (GPS SESSION PT. NO. 43) ( THIS WELL WAS NO.W-5 ON THE LEASE MAP. )

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

  
TECHNICIAN