


15-065-00184-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD



Graham County. Sec. 18 Twp. 6 Rge. 23 (E) W (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines NE NE NE
Lease Owner B & R Drilling, Inc.
Lease Name Kellogg Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 11, 1951 19
Application for plugging filed June 10, 1951 Verbally 19
Application for plugging approved June 10, 1951 Verbally 19
Plugging commenced June 11, 1951 19
Plugging completed June 11, 1951 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 4101' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8 "	212'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging Record

Fill with heavy mud to 200' set wooden plug @ 200'.
15 sacks cement through drill pipe, mud to 40' Wooden
plug at 40'. 1/2 Sacks hulls and 10 sacks cement.
Tie top plug to surface pipe.

RECEIVED
STATE CORPORATION COMMISSION
JUN 19 1951
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to B & R Drilling, Inc.
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
W. A. Michaelis, Jr. (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. A. Michaelis, Jr.
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of June, 19 51
Clara Lumme
Notary Public.

My commission expires 6-17-54

PLUGGING
FILE SEC-18T-6-R-236
BOOK PAGE 88 LINE 25

15-009-00184-06-00

Dan Kornfeld - B & R Drilling, Inc.
Kellogg No. 1

NE NE NE Section 18-6-23
Graham County, Kansas

Total Depth: 4101'
Comm: 5-30-51
Comp: 6-11-51

Casing

Cement

8 5/8" Set @ 212'

125 Sacks Cement

Formation	Depth
Surface Clay-Shale	40
Shale	80
Sand-Shale	170
Shale-Shells	212
Shale-Sand	260
Shale-Shells	600
Sand-Shale	650
Shells-Shale	1675
Redbed	1790
Shale-Shells	2020
Sandy Shale-Redbed	2125
Anhydrite	2160
Shale-Shells	2515
Shale-Lime	3700
Lime	3915
Marmaton Shale	3960
Shale-Lime	4045
Marmation Shale	4088
Arbuckle	4101

STATE OF KANSAS)
)SS
RUSSELL COUNTY)

I hereby certify that the above information is true
and correct to the best of my knowledge.

Violet Keller

Subscribed and sworn to before me this 18th day of June, 1951.

Mrs. Sumner
Notary Public

My commission expires: 6-17-54

PLUGGING
FILE SEC 18-6-23
BOOK PAGE 28 LINE 25

RECEIVED
STATE CORPORATION COMMISSION
JUN 19 1951 6-19-51
DIVISION
Wichita, Kansas