

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-20,883 -0000

LEASE NAME Walters

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

660 Ft. from S Section Line

3300 Ft. from E Section Line

LEASE OPERATOR Dyco Petroleum Corporation

SEC. 32 TWP. 6S RGE. 23 (S or W)

ADDRESS 7130 S. Lewis, Suite 300, Tulsa, Okla 74136

COUNTY Graham

PHONE#(918) 496-7600 OPERATORS LICENSE NO. _____

Date Well Completed 12-14-76
~~4-14-87~~

Character of Well oil

Plugging Commenced 9-29-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-30-87

The plugging proposal was approved on September 29, 1987 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? To Plugging Application 3982-DTD

Producing Formation Burlington, Lansing Depth to Top 3422 Bottom 3843 T.D. 3950 PBTD

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Burlington	Dry	3422	3426	4-1/2	3982	none
Lansing	Dry	3768	3843			
surface	-----	---	---	8-5/8	315	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Model T bridge plug set on sandline @ 3395'. Loaded hole. Perforated 3 shots @ 2220' and 3 shots @ 1330'. Pump 250 sx Halliburton econolite (Hayes mix) w/ 4 sx cottonseed hulls. (pumped 150 sx down 4 1/2 leaving plug from 2220' to surface and pumped 100 sx down 8 5/8/74 1/2 annulus. Cut off casing and

(If additional description is necessary, use BACK of this form.)

welded on plate with name and date. Witnessed by Carl Goodrow-District 4.
Name of Plugging Contractor Murfin Drlg Co License No. _____

Address 250 N. Water Suite 300 Wichita, Kansas 67202 10-1-1988

STATE OF Kansas COUNTY OF Graham, ss. 1-4-88

Dyco Petroleum Corporation (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ray A. Hea

(Address) 7130 S. Lewis, #300, Tulsa, OK 74136

SUBSCRIBED AND SWORN TO before me this 30th day of December, 19 87

Kelra Lynn Baker
MY COMMISSION EXPIRES OCTOBER 28, 1991 Notary Public

My Commission Expires: _____