

15-065-00080-00-00
WELL PLUGGING RECORD


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
of formations.

Graham County, Sec. **34** Twp. **6** Rge. **23** (#) **(#)** (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines **SW SW SW**
Lease Owner **Anderson-Prichard Oil Corporation**
Lease Name **Dietz** Well No. **1**
Office Address **Route #1, West 10th, Great Bend, Kansas**
Character of Well (completed as Oil, Gas or Dry Hole) **Dry Hole**
Date well completed **July 23** 19 **48**
Application for plugging filed **August 4** 19 **48**
Application for plugging approved **Verbal July 23** 19 **48**
Plugging commenced **July 23** 19 **48**
Plugging completed **July 23** 19 **48**
Reason for abandonment of well or producing formation
Dry Hole
If a producing well is abandoned, date of last production **None** 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? **Yes**



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well **M. A. Rives**
Producing formation..... Depth to top..... Bottom..... Total Depth of Well **4143'** Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	313'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Hole filled with heavy mud 4143' to 316'
15 Sax cement 316' to 276'. Halliburton Plug at 276'
Filled with heavy mud 276' to 35'. Halliburton Plug at 35'
10 Sax cement 35' to 0

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to **W. J. Dearen**
Address **Anderson-Prichard Oil Corp. Route #1, West 10th, Great Bend, Kansas**

STATE OF **Kansas**, COUNTY OF **Barton**, ss.
Gerald M. Dougherty (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Gerald M. Dougherty*
(Address)

SUBSCRIBED AND SWORN to before me this **4th** day of **August**, 19 **48**

Henry Peacock
Notary Public.

My commission expires **June 13, 1951**

22-287 7-47-10M

PLUGGING
FILE SEC 34 T 6 R 30
PAGE 46 LINE 15

DRILLERS LOG OF FORMATIONS

ANDERSON-RICHARD OIL CORPORATION

DIETZ NO. 1

SW/4 SW/4 SW/4 Sec. 34-69-23W

Graham County, Kansas

<u>FORMATION DRILLED</u>	<u>FROM</u>	<u>TO</u>	
Surface Clay	0	40	
Sand	40	100	
Shale and Shells	100	1060	Set 8-5/8" casing @
Sand	1060	1300	316' and Cemented w/
Shale and Shells	1300	2085	175 Sks. Cement.
Anhydrite	2085	2115	
Shale and Shells	2115	2750	
Shale and Lime	2750	3715	
Lime	3715	3935	
Shale and Lime	3935	4103	
Lime	4103	4143	

T.D. - D.A.

Plugging Record

Heavy Mud 4143' to 316'
 15 Sks Cement 316' to 276'
 Halliburton Plug 276'
 Heavy Mud 276' to 35'
 Halliburton Plug 35'
 10 Sks Cement 35' to 0

CONTRACTOR: TRANSIT CORPORATION
 3111 Apco Tower
 Oklahoma City, Okla.

I hereby certify the foregoing to be a true and correct
 driller's log of the formations encountered in the above well.

TRANSIT CORPORATION

By *L. F. Young*
 L. F. Young
 Assistant Secretary

Subscribed and Sworn to before me this 2nd day of August, 1948

By *Hazel Turley* My commission expires March 13, 1949
 Hazel Turley (Notary Public)

PLUGGING
 FILE NO. 34-69-23W
 BOOK PAGE 461-15

948

8-5-48