


15-065-00797-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Graham County. Sec. 36 Twp. 6S Rge. 23W (E) (W)
Location as "NE/CNW/SW" or footage from lines C SE SE
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Trexler "B" Well No. 1
Office Address 780 Fourth National Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed March 19 19 59
Application for plugging filed November 13 19 59
Application for plugging approved November 18 19 59
Plugging commenced November 25 19 59
Plugging completed November 29 19 59
Reason for abandonment of well or producing formation Commercial quantities of oil depleted.

If a producing well is abandoned, date of last production November 25 19 59
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3803 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	216'	
				5-1/2"	3803'	3803'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole to 215', set 10' rock bridge. Mixed and run 25 sacks cement, mud to 40' - set 10' rock bridge and 10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JAN 19 1960
1-19-1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address P. O. Box 364, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Raymond L. Bacon (employee of ~~owner~~ or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: Ray L. Bacon V-P
780 Fourth National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of January, 19 60

My commission expires July 7, 1962
Mona L. Latier
Mona L. Latier Notary Public.

15-065-00797-00-00

RECEIVED
STATE COMMISSION
JAN 19 1960
CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Building
Wichita 2, Kansas

Trexler "B" No. 1
C SE SE Sec. 36-6S-23W
Graham County, Kansas

Total Depth: 3803'

Commenced: 2-23-59 Completed: 3-5-59

Elevation: 2361' RB
Production:

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 216' with 165 sacks cement.
Set 5-1/2" Production Pipe at 3803' with 125 sacks cement.

Figures indicate bottom of formations:

		<u>TOPS</u>	
Sand & Shale	216'	Anhydrite	2014' (/ 347)
Shale & Shells	1440'	Heebner	3572' (-1211)
Sand-Shale & Shells	2014'	Toronto	3596' (-1235)
Anhydrite	2050'	Lansing	3612' (-1251)
Shale & Shells	2325'	Rotary Total Depth	3803' (-1442)
Shale & Lime	3620'		
Lime	3803'		
Total Depth	3803'		

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: A. L. Brown
Vice-President

Subscribed and sworn to before me this 7th day of April, 1959.

My Commission Expires:

July 7, 1962

Mona L. Latier
Mona L. Latier-Notary Public