

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,662-00-00

LEASE NAME Augustine

WELL NUMBER 1

4280 Ft. from S Section Line

2970 Ft. from E Section Line

SEC 14 TWP. 6 RGE. 24 ~~XX~~ or (W)

COUNTY Graham

Date Well Completed 4/7/92

Plugging Commenced 4/7/92

Plugging Completed 4/7/92

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Hess Oil Company

ADDRESS P. O. Box 1009, McPherson, KS 67460

PHONE # (316) 241-4640 OPERATORS LICENSE NO. 5663

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/6/92 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4210 Ft.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation Surface	Content	From	To	Size	Put in	Pulled out
		248	0'	8-5/8"	248'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged hole with 225 sx 60/40 Pozmix, 6% gel, 1/2# floseal/sk as follows:

25 sx @ 4170', 25 sx @ 2160', 100 sx @ 1300', 40 sx @ 280', 10 sx @ 40',

15 sx RH, 10 sx MH. P.D. @ 7:35 a.m. 4/7/92.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard JV, Inc. License No. 4958

Address P. O. Box 1009, McPherson, KS 67460

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hess Oil Company

STATE OF KANSAS COUNTY OF MCPHERSON

James H. Hess

(Employee of _____) or (Owner of _____)


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James H. Hess

(Address) same

SUBSCRIBED AND SWORN TO before me this 21st day of April, 19 92

My Commission Expires: _____



RECEIVED
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION
SEP 10 1992
9-10-92
CONSERVATION DIVISION
Wichita, Kansas

MAY 14 1992
CONSERVATION DIVISION
Wichita, Kansas

CCC
JUL 23 1992
Wichita, KS