


15-065-00877-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 8 Twp. 6 Rge. (E) 24 (W)
Location as "NE/CNW/SW" or footage from lines NW NW NE
Lease Owner Musgrove Petroleum Corporation
Lease Name LOGUE Well No. 1
Office Address 518 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed March 27, 1956
Application for plugging filed verbally March 26, 1956
Application for plugging approved verbally March 26, 1956
Plugging commenced March 27, 1956
Plugging completed March 27, 1956
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes- verbally

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4140 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	226'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 220'
Set 1st Plug at 220' w/ 1/3 sk hulls & 15 sx cement.
Filled hole with heavy mud to 40'
Set 2nd Plug at 40' w/ 1/3 sk hulls & 10 sx cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Musgrove Petroleum Corporation
Address 518 Petroleum Building, Wichita, Kansas.

STATE OF Kansas COUNTY OF Sedgwick
I, Gordon L. Koelling, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
518 Petroleum Building, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of March, 19 56

My commission expires June 16, 1959.

Reah Joyce Depke
Notary Public.

PLUGGING
FILE SEC 8 T 6 R 24W
BOOK PAGE 49 LINE 13

3-29-56
CORPORATION
WICHITA, KANSAS

CONTRACTOR'S WELL LOG

COMPANY:	Musgrove Petroleum Corporation
CONTRACTOR:	Musgrove Petroleum Corporation
FARM:	LOGUE #1
LOCATION:	NW NW NE Section 8-6-24 Graham County, Kans.
COMMENCED:	March 14, 1956
COMPLETED:	March 27, 1956

0	215	Surface soil & sand
215	900	Shale & shells
900	2090	Shale, shells & sand
2090	2125	Anhydrite
2125	2155	Shale
2155	2495	Shale & lime
2495	2650	Shale & lime streaks
2650	3025	Lime & shale
3025	3100	Lime
3100	3520	Shale & lime
3520	3810	Lime
3810	4005	Shale & lime
4005	4070	Shale, lime & chert
4070	4140	Lime & shale
	4140	Rotary Total Depth

Set 8-5/8" surface casing at 226' with 175 sacks cement, 2% calcium chloride.
Dry and Abandoned.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the LOGUE #1, NW NW NE, Section 8-6-24, Graham County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY *Gordon L. Koelling*
Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 28th day of March, 1956.

Leah Joyce Hoyer
Notary Public

My commission expires June 16, 1959.

PLUGGING
NW 8 T 6 R 24W
MOE 49 LINE 13