

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

MAR 04 2005

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Marlin Oil Corporation  
Address: Box 14630 OKC OK 73113  
Phone: (405) 478-1900 Operator License #: 9228  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 12-10-04 RCC BEN OS RBDMs (Date)  
by: Steve Durrant (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Morrow Depth to Top: 5570 Bottom: 5578 T.D. \_\_\_\_\_  
Morrow Depth to Top: 5737 Bottom: 5770 T.D. 6170  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-175-21404-00-00  
Lease Name: Bryant B  
Well Number: 5-8  
Spot Location (QQQQ): \_\_\_\_\_ - NE - NE  
660 Feet from  North /  South Section Line  
660 Feet from  East /  West Section Line  
Sec. 8 Twp. 33 S. R. 33  East  West  
County: Seward  
Date Well Completed: 8-4-94  
Plugging Commenced: 2-2-05  
Plugging Completed: 2-3-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>Morrow</u>	<u>gas</u>			<u>8 5/8</u>	<u>1520</u>	<u>-</u>
				<u>5 1/2</u>	<u>6124</u>	<u>2423</u>

RECEIVED  
APR 11 2005  
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 300 lb hulls to 25 sx cmt. to plug perfs from 5570 to 5370. Shot & pulled to 1530. Circ. hole w/mud & mixed 50 sx plug from 1530 to 1380 30 sx 660 to 560 10 sx 40 to 0 Capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151  
Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731  
Name of Party Responsible for Plugging Fees: MARLIN OIL CORP

State of \_\_\_\_\_ County, \_\_\_\_\_, ss.  
W.R. Lynn (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



W.R. Lynn (Signature)  
Notary Public in and for  
State of Oklahoma (Address)  
Oklahoma City, Ok  
SUBSCRIBED and SWORN to before me this 7 day of April, 2005  
Carla Parker (Signature)  
Notary Public My Commission Expires: 4/26/07