

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION
Address: 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226
Phone: (316) 682-1537 Operator License #: 5030
Type of Well: D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 3/23/05 (Date)
by: Ron Rowe - District #3 (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 2877 Bottom: 2880 T.D. 2880
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 049-22414-00-00
Lease Name: Perkins
Well Number: #1-20
Spot Location (QQQQ): _____ - SW - NE - SW
1530" Feet from North / South Section Line
1770" Feet from East / West Section Line
Sec. 20 Twp. 29S S. R. 09 East West
County: Elk
Date Well Completed: 3/22/05
Plugging Commenced: 3/23/05
Plugging Completed: 3/23/05

KCC
BEM
4-15-05
KED MS

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	sw, sli oil	2877'	2880'	8-5/8"	71	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Cement plugs pumped thru drill pipe: 60/40 pozmix, 4% gel; 2870' = 30 sx.; 2710' to 450' drilling mud;
450' to 0' = 140 sx. Circ. cement to surface. Rat hole = 25 sx. Consolidated Ticket #3546

Name of Plugging Contractor: C & G Drilling Company License #: 32701
Address: P.O. Box 229, Eureka, KS 67045
Name of Party Responsible for Plugging Fees: Vess Oil Corporation
State of Kansas County, Sedgwick, ss.
W.R. Horigan


RECEIVED
APR 15 2005
KCC WICHITA

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) WR Horigan
(Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED and SWORN TO before me this 12th day of April 2005

Michelle D. Henning My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

BW

CONSOLIDATED OIL WELL SERVICES, INC.
 211 W. 14TH STREET, CHANUTE, KS 66720
 620-431-9210 OR 800-467-8676

ATT
 Casey Coats

TICKET NUMBER 3546
 LOCATION Eureka
 FOREMAN Brad Butler

TREATMENT REPORT & FIELD TICKET
 CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
3-23-05		Perkins #1-20	20	29s	9E	EIK
CUSTOMER Vess Oil Corporation			CIG Drilling CO.			
MAILING ADDRESS 8100 E. 22nd Street North, Bldg. 300						
CITY Wichita	STATE Ks.	ZIP CODE 67226	TRUCK #	DRIVER	TRUCK #	DRIVER
			446	Rick		
			440	Scott		

JOB TYPE P.T.A. HOLE SIZE 7 7/8" HOLE DEPTH 2880' CASING SIZE & WEIGHT _____
 CASING DEPTH _____ DRILL PIPE 4" TUBING _____ OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
 DISPLACEMENT _____ DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety Meeting: Reinspect Drill Pipe, Spot cement Plugs as follows:

30 SKs Plug at 2870'
140 SK. Plug at 450' To Surface
25 SK. Plug in R.H.
195 SKs 60/40 Perm mix w/ 4% Gel Total

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405 N	1	PUMP CHARGE	750.00	750.00
5406	30	MILEAGE	2.45	73.50
1131	195 SKs	60/40 Perm mix cement	7.80	1521.00
1118	7 SKs	Gel 4%	13.00	91.00
5407A	8.4 Tow	30 miles - Bulk Truck	.90	226.80
RECEIVED				
APR 15 2005				
KCC WICHITA				
			6.3%	SALES TAX
				101.55
				ESTIMATED TOTAL
				2763.85

AUTHORIZATION Witnessed by Tim Goulick TITLE CIG Drilling CO. DATE _____