

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15 - 065-21136-0000 (of this well)
Lease Owner Beren Corporation
Address 970 Fourth Financial Center, Wichita, Kansas 67202
Lease (Farm Name) ROBERTS Well No. 1
Well Location NW NE SW Sec. 30 Twp. 6S Rge. 25W (E) (W)
County Graham Total Depth 3950' Field Name _____
Oil Well Gas Well Input Well SWD Well Rotary D & A
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 10:00 a.m., 09-27-79

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Bill Craig Address 702 So. 2nd Street, Hill City, Ks

Plugging Contractor Abercrombie Drilling, Inc. License No. _____

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Beren Corporation

Address 970 Fourth Financial Center, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

RECEIVED
STATE CORPORATION COMMISSION
OCT - 4 1979
16-4-79
CONSERVATION DIVISION
Wichita, Kansas

Signed: Jack L. Partridge
Applicant or Acting Agent
Jack L. Partridge
Date: October 2, 1979

13-065-21136-00-00

CONTRACTOR'S WELL LOG

OPERATOR: Beren Corporation
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Roberts #1
 LOCATION: NW NE SW, Section 30-6S-25W
 Graham County, Kansas
 SPUD DATE: September 20, 1979
 COMPLETION DATE: September 27, 1979

0	331	Clay, sand and shale
331	1242	Shale
1242	2216	Shale and sand
2216	2249	Anhydrite
2249	2370	Shale
2370	2820	Lime and shale
2820	3055	Shale and lime
3055	3808	Lime and shale
3808	3835	Lime
3835	3950	Lime and shale
	3950	Rotary Total Depth

Spud hole at 1:00 p.m., September 20, 1979. Drilled 331' of 12 1/4" hole. Ran 7 joints of 8-5/8" - 28# used casing. Set at 330' with 225 sacks of 60/40 posmix, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 6:15 p.m., September 20, 1979.

T.D. 3950'. Set 1st plug at 1320' with 60 sacks, 2nd plug at 330' with 30 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 10:00 a.m., September 27, 1979.

SAMPLE TOPS:

Anhydrite 2216'
 B/Anhydrite 2249'

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

RECEIVED
 STATE CORPORATION COMMISSION
 OCT - 4 1979
 CONSERVATION DIVISION
 Wichita, Kansas
 16-4-79

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Roberts #1, NW NE SW, Section 30-6S-25W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 2nd day of October, 1979.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 08-21-82.

State of Kansas



15-065-21136-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water

WICHITA, KANSAS 67202

Telephone (316) 263-3238

October 2, 1979

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Roberts
Description	NW NE SE Sec. 30-6S-25W
County	Graham
Total Depth	3950'
Plugging Contractor	Abercrombie Drilling, Inc.


Beren Corporation
970 Fourth Financial Center
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Marion Schmidt, 2104 Canterbury Rd., Hays, Kansas 67601
is hereby assigned to supervise the plugging of the above
named well.