

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
800 BITTING BUILDING  
WICHITA, KANSAS

15-065-00269-00-00

WELL PLUGGING APPLICATION FORM

Lease Owner Harry Gore Address 100 Brown Bldg., Wichita, Kansas  
(Applicant)

Lease (Farm Name) Cook Well No. 1

Well Location NE NE NE Sec. 28 Twp. 6 Rge. (E)-(W) 25

County Graham Field Name (if any) \_\_\_\_\_

Total Depth 1250 Oil \_\_\_\_\_ Gas \_\_\_\_\_ Dry Hole X

Was well log filed with application? \_\_\_\_\_. If not, explain: \_\_\_\_\_

\_\_\_\_\_ Log will be filed with application.

Date and hour plugging is desired to begin July 7, 1951 8:00 a.m.

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully any exceptions desired.  
(Use an additional sheet if necessary) \_\_\_\_\_

Name of the person on the lease in charge of well for owner \_\_\_\_\_

L. E. Bernd Address P. O. Box 229, McPherson, Kansas

Name of Plugging Contractor Veeder Supply & Development Company

Address P. O. Box 201, Cherryvale, Kansas

Invoice covering assessment for plugging this well should be sent to

Harry Gore Address 100 Brown Bldg., Wichita, Kansas

and payment will be guaranteed by applicant.

**PLUGGING**  
FILE SEC 28 T 6 R 25  
BOOK PAGE 92 LINE 44

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 20 1951  
[Signature]  
Applicant or Acting Agent

Date July 7, 1951

13-065-00269-00-00

Company Harry Gore

Sec. 28 T. 6 R. 25

Loc. NE NE NE

Farm Cook

No. 1

County Graham County, Kansas

Total Depth 4250'

Comm. 6-25-51

Comp. 7-7-51

Shot or Treated

Contractor Veeder Supply Company

Drilled with Rig - D

Issued

No. of Days - 13

Casing

No. of Bits -

20 in. 10 in

15 1/2 8 1/4


12 1/2 6 5/8

13 3/8 5 3/16

Set 280' of 8-5/8" Casing Cemented with 175 sacks cement.

Elevation

Production




Figures Indicate Bottom of Formation

Surface Soil Clay	0	30	30
Sand	30	277	247
Shale	277	300	23
Blue Shale Shells	300	600	300
Shale Shells	600	1100	500
Sand Shale	1100	1200	100
Shale Shells	1200	1260	60
Sand Shale	1260	1550	290
Shale Shells	1550	1800	250
Sand Shale	1800	1925	125
Shale Shells	1925	2075	150
Red Bed Shale	2075	2180	105
Anhydrite	2180	2220	40
Shale Shells	2220	2690	470
Line Shells Shale	2690	2715	25
Shale Line	2715	3075	360
Line	3075	3100	25
Shale Line	3100	3155	55
Line	3155	3885	730
Line Shale	3885	3925	40
Sandy Shale	3925	3940	15
Line Shale	3940	4020	80
Line	4020	4045	25
Conglomerate	4045	4105	60
Line Shale	4105	4155	50
Conglomerate Cherty	4155	4227	72
Line	4227	4250	23
Total Depth	4250'		

Tops:

Topeka	- 3434
Heebner Shale	- 3639
Dodge	- 3710
Lansing K.C.	- 3725
Base K.C.	- 3917
Conglomerate	- 4158
Arbuckle	- 4227

Plugged @ 250' with 15 sacks cement.  
Plugged @ 40' with 10 sacks cement.



RECEIVED  
STATE GEOLOGICAL SURVEY  
CONSERVATION DIVISION

JUL 20 1951

CONSERVATION DIVISION  
Wichita, Kansas

7-20-51



STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
800 BITTING BUILDING  
WICHITA, KANSAS

15-065-00269-00-00

July 9, 1951

Well No.	1
Lease	Cook
Description	NE NE NE 20-6-25W
County	Graham
File No.	92-14

Mr. Harry Gore  
100 Brown Bldg.  
Wichita, Kansas

Dear Sir:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Eldon Petty, Box 326, Hays, Kansas.

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION

BY: J. P. Roberts  
J. P. ROBERTS

cc: DISTRICT PLUGGING SUPERVISOR