

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15-065-21146-00-00 (of this well)
Lease Owner F & M Oil Company
Address 505 Union Center, Wichita, Kansas 67202
Lease (Farm Name) Kline Well No. 1
Well Location C NW NW Sec. 21 Twp. 6 Rge. 25W (E) (W) X
County Graham Total Depth 3915' Field Name
Oil Well Gas Well Input Well SWD Well Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 2:30 a.m., 8-29-79

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Harold Maley Address 216 E. McFarland, Hill City, Ks

Plugging Contractor Abercrombie Drilling, Inc. License No.

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name F & M Oil Company

Address 505 Union Center, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge
Applicant or Acting Agent

Jack L. Partridge
Date: September 4, 1979

RECEIVED
STATE CORPORATION COMMISSION
9-6-79
SEP - 6 1979

CONSERVATION DIVISION
Wichita, Kansas

15-065-21146-00-00

CONTRACTOR'S WELL LOG

OPERATOR: F & M Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Kline #1
 LOCATION: C NW NW, Section 21-6-25
 Graham County, Kansas
 SPUD DATE: August 23, 1979
 COMPLETION DATE: August 29, 1979

0	97	Shale and surface clay
97	302	Sand and shale
302	365	Shale
365	1958	Shale and sand
1958	2170	Shale
2170	2204	Anhydrite
2204	2836	Shale
2836	3050	Shale and lime
3050	3625	Lime and shale
3625	3915	Lime
	3915	Rotary Total Depth

Spud hole at 2:00 p.m., August 23, 1979. Drilled 232' of 12 1/4" hole. Ran 11 joints of 8-5/8" - 28# used casing. Set at 230' RTD with 270 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 8:30 p.m., August 23, 1979.

T.D. 3915'. Set 1st plug at 1200' with 70 sacks, 2nd plug at 300' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 2:30 a.m., August 29, 1979.

SAMPLE TOPS:

Anhydrite 2170'
 B/Anhydrite 2204'

RECEIVED
 STATE CORPORATION COMMISSION

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

SEP - 6 1979
 9-6-79
 CONSERVATION DIVISION
 Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Kline #1, C NW NW, Section 21-6-25, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 4th day of September, 1979.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 08-21-82.

State of Kansas



15-065-21146-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202
Telephone (316) 263-3238

September 5, 1979

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Kline
Description	C NW NW (21-6S-25W)
County	Graham
Total Depth	3915'
Plugging Contractor	Abercrombie Drilling Inc.


F & M OIL Company, Inc.
505 Union Center
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Gilbert Balthazor, Box 9, Palco, Kansas 67657
Is hereby assigned to supervise the plugging of the above named well.