

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
Wichita, Kansas 67217

Rev. 3-15-72  
FORM CP-1

RECEIVED  
STATE CORPORATION COMMISSION

WELL PLUGGING APPLICATION FORM  
File One Copy

JAN 27 1975  
01-27-75  
CONSERVATION DIVISION  
Wichita, Kansas

15-179-05297-00-01

Lease Owner PETROLEUM MANAGEMENT, INC.

Address 400 N. WOODLAWN, SUITE 201, WICHITA, KANSAS 67208

Lease (Farm Name) ADELL Well No. 301

(SW SW SW)

Well Location SW/4 Sec. 7 Twp. 6S Rge. (E) (W) 26

County Sheridan Total Depth 3819' Field Name ADELL

Oil Well      Gas Well      Input Well XX SWD Well      Rotary D & A     

Well Log filed with application as required attached

Date and hour plugging is desired to begin unknown.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

DONALD H. KEENER Address 2305 WALNUT, HAYS, KANSAS 67601

Plugging Contractor PETROLEUM MANAGEMENT, INC. License No. 731

Address P. O. BOX 1325, GREAT BEND, KANSAS 67530

Invoice covering assessment for plugging this well should be sent to:

Name PETROLEUM MANAGEMENT, INC.

Address P. O. BOX 1325, GREAT BEND, KANSAS 67530

and payment will be guaranteed by applicant or acting agent.

Signed:   
Applicant or Acting Agent

Date: JAN. 23, 1975

15-109-05297-00-01

IMPERIAL OIL KANSAS, INC.  
Well Completion Report

Randolph Lease. Well No. 1  
Loc. SW SW SW Sec. 7 Twp. 6S Rge. 26W  
County Sheridan State Kansas  
Pool Adell

Spud Date ..... 12-19-55  
Rotary Completed 1-4-56  
Completion Date 1-13-56  
Potential ..... 91 BOPD  
Gravity ..... 38.1  
R. T. D. 3819

Surface casing set at (8 5/8) 323 with 225 sacks  
Production casing set at (5 1/2) 3819 with 125 Sacks

Formation Tops:  
Elevation: 2575 RB

Sample	Electric Log	Produced To
Anhydrite 2123 (A452)	Yes	Jan. 1957 5,775
Heebner 3569 (-994)		Jan. 1958
Lansing 3611 (-1036)		Jan. 1959
Base KC 3810 (-1235)		Jan. 1960
		Jan. 1961
		Jan. 1962
		Jan. 1963
		Jan. 1964
		Jan. 1965
		Jan. 1966
		Jan. 1967

PRODUCING AND PROSPECTIVE PRODUCING ZONES

Formation	Depth	Feet	Remarks	Estimated Reserves
Perf. 35'	3628-32		Open	
Perf. 90'	3669-72	11	Open	10,689
Perf. 200'	3766-68		Open	

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 27 1975  
CONSERVATION DIVISION  
Wichita, Kansas

Completion Date: 1-5-56  
Moved unit in; rigged up.  
1-6-56  
Finished rigging up. Swabbed well to TD of 3799  
1-7-56  
Ran Halliburton log to TD. Perf. 200' zone with 16 holes from 3766-68 using Halliburton 1/2" bullets. Acidized with 1000 gal. J-type acid by Chemical Process. Highest pressure used 500# Feeding pressure 450#. Pressure drop 450# to 400# in 10 min. Swabbed well to TD.  
1-8-56  
16 hr. swab test off bottom showed 10 BOPH - NW Retreated with 3000 gal. J-type / 2000 gal. Jel acid by Chemical Process. Highest pressure used 550#. Feeding pressure 550#. Pressure drop 550# to 300# in 10 min.

1-9-56  
16 hr. swab test off bottom showed 2 1/2 BOPH - NW, 12 hours of test, then falling to 1.62 BOPH - NW Perf. the 90' zone with 18 holes from 3669-72. using Halliburton 1/2" bullets. Set retrievable Baker plug at 3700. Acidized with 1000 gal. J-type acid by Chemical Process. Highest pressure used 200#. Feeding pressure 200#. Pressure drop 200# to 0# in 1 min. Swabbed well down.  
1-10-56  
12 hr. swab test showed well making 3 BOPH - NW Retreated with 3000 gal J-type acid by Chemical Process. Highest pressure 250#. Feeding pressure 250#. Pressure drop 250# to 125# in 5 min. Swabbed well down.  
1-11-56  
8 hr. swab test showed 3.36 BOPH - NW. Retrieved Baker plug. Perf. the 35' zone with 20 holes from 3628-32 using Halliburton 1/2" bullets. Reset Baker plug at 3650. Acidized with 1000 gal. J-type acid by Chemical Process. Well treated on a vacuum. Swabbed well down.

State of Kansas



15-179-05297-00-01

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

January 27, 1975

WELL PLUGGING AUTHORITY

Well No.	301
Lease	Adell
Description	SW SW SW 7-6-26W
County	Sheridan
Total Depth	3819'
Plugging Contractor	Petroleum Management, Inc.


Petroleum Management, Inc.  
P. O. Box 1325  
Great Bend, Kansas 67530

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,

  
J. Lewis Brock, Administrator

Mr. Dale Balthazor, 189 First Street, Phillipsburg, Kansas 67661  
is hereby assigned to supervise the plugging of the above  
named well.