

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01010-00-01
Spot: NENESW Sec/Twnshp/Rge: 4-9S-21W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease Name: NAPUE Well #: 1
County: GRAHAM Total Vertical Depth: 3810 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

CIBP Size: feet: 3694
PROD Size: 5.5 feet: 3809 200 SX CMT
SURF Size: 8.625 feet: 180 UNKNOWN

#12383

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/13/2005 11:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: STEVE BAIZE Company: CHARTER ENERGY, INC. Phone: (785) 623-1861

Proposed Plugging Method: Ordered out 125 sxs Swift Multi-Density Cement - 500# hulls - 18 sxs gel.
PC at 1640' set with 300 sxs.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/13/2005 2:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Swaged onto 5 1/2" - mixed and pumped 30 sxs SMD cement with 500# hulls, followed with 18 sxs gel.
Topped with 70 sxs cement.
Max. P.S.I. 600#. S.I.P. 400#.
Hooked up to the annulus and pumped 5 sxs cement.
S.I.P. 150#.

Perfs:

Top	Bot	Thru	Comments
3729	3732		
3668	3681		
3558	3560		

RECEIVED
APR 18 2005
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

ND

Signed Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE 4-18-05

TV. NO. 2005061423

APR 14 2005

REPLACEMENT CARD

BROUGHER OIL, INC.
P.O. DRAWER 1367

4-9-21W
NE NE SW

GREAT BEND, KS. 67530
CONTR MOHAWK DRILLING

#1 NAPUE DW/O

CTY GRAHAM

GEOL LARRY BOOKLESS

WINDY

FIELD MORE (N) FIELD DISC-

POOL #2-NP 48546

+	+	+
+	+	+
+	+	+

ELV 2172 KB SPD 1/15/85 CARD ISSUED 6/27/85
2169 GL DRLG COMP 1/19/85
API 15-065-01,010

IP P 25 BO & 10 BWPD
MARM 3669-3681

LOG	Tops	Depth/Datum
ANH	1635+ 537
B/ANH	1668+ 504
TOP	3119- 947
HEEB	3329-1157
TOR	3353-1181
LANS	3370-1198
BKC	3580-1408
MARM	3616-1444
CONG	3682-1510
ARB	3729-1557
PBTD	3694-1522
ORTD	3738-1566
LTD&DDTD	3810-1638

OLD INFO: OPERATOR WAS BARNETT DRILLING CO., #1 NAPUE, SPD 12/16/49, SET 8 5/8 " 180. COMP AS D&A/ARB (CARD ISSUED 12/30/49), CONTR: COMPANY TOOLS
NO CORES
DST (1) 3675-3738 (ARB) / 45-60-45-60, REC 125' OCM, SIP 1043-1078#, FP 70-87 / 87-122#, HP 2041-2970#, BHT 110"
DST (2) 3534-3577 (LKC, W/HW) / MISRUN, PKR FAILED
DST (3) 3532-3575 (LKC, W/HW) / MISRUN, PKR FAILED
NEW INFO: FR 12/19/84, RE-ENTERED 1/15/85, WSH DOWN TO ORTD, DD 3810 TD, DRLG COMP 1/19/85, SET 5 1/2 " 3809 / 200SX, MICT - CO, PF (ARB) 3724-3732, W / 3 SPF, AC 300 GAL (15% MCA), FU 1200' FL (TOP 200', SLI SO) / 48 HRS, SET CIBP AT 3694, PF (MARM) 3669-3681, W / 3 SPF, AC 750 GAL (15% DBL STRENGTH FE), GSO, SET 2 7/8 " TBG AT 3690, POP, P 25 BO & 10 BWPD, 2/27/85

INFO RELEASED: 7/10/86 - WAS OIL WELL - TIGHT HOLE