

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22221-00-00
Spot: SWNESW Sec/Twnshp/Rge: 4-9S-21W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease Name: NAPUE Well #: 3
County: GRAHAM Total Vertical Depth: 3810 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

PROD Size: 5.5 feet: 3809 450 SX CMT
SURF Size: 8.625 feet: 304 225 SX CMT

A 123⁸³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2005 2:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: STEVE BAIZE Company: CHARTER ENERGY, INC. Phone: (785) 623-1861

Proposed Plugging Method: Ordered out 125 sxs Swift Multi-Density Cement - 500# hulls - 18 sxs gel.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/12/2005 3:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Swaged onto 5 1/2" - mixed and pumped 30 sxs SMD cement with 500# hulls, followed with 18 sxs gel.
Topped with 55 sxs cement.
Max. P.S.I. 400#. S.I.P. 325#.
Hooked up to the annulus and pumped 15 sxs cement.
S.I.P. 150#.

Perfs:

Top	Bot	Thru	Comments
3740	3748		
3495	3497		

RECEIVED
APR 18 2005
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

187

Signed Jay Pfeifer (TECHNICIAN)


INVOICED
DATE 4-18-05
TV. NO. 2005067423

APR 14 2005

BROUGHER OIL, INC.
P.O. BOX 1367
GREAT BEND, KS. 67530
CONTR MOHAWK DRILLING
GEOLOGICAL KEVIN E. ADAMS

REPLACEMENT GARD
#3 NAPUE
4-9-21W
SW NE SW

MAHOLET
GRAHAM
MOREL



ELV 2213 KB SPD 9/3/85 CARD ISSUED 11/21/85 P 20 BOPD, NW
2203 GL DRLG COMP 9/12/85 ARB 3740-3748
API 15-065-22,221

LOG	Tops	Depth/Datum
ANH		1670+ 543
B/ANH		1702+ 511
HOW		3109- 896
TOP		3156- 943
HEEB		3370-1157
TOR		3391-1178
LANS		3408-1195
BKC		3622-1409
MARM		3640-1427
FT SC		3711-1498
CHER		3721-1508
ARB		3725-1512
LTD		3808-1595
RTD		3810-1597

8 5/8 " 304 / 225 SX, 5 1/2 " 3809 / 450 SX
NO CORES
DST (1) 3438-3457 (LANS C&D) / 30-30-30-30, REC 5' M, SIP 1042-1022#, FP 20-29 / 29-29#, HP 1807-1817#, BHT 97°
DST (2) 3613-3727 (MARM, FT SC) / 30-30-30-30, REC 7' M, SIP 244-176#, FP 68-88 / 88-88#, HP 1953-1962#, BHT 99°
DST (3) 3722-3753 (ARB) / 45-45-45-45, REC 217' HOCM (40% OIL, 60% M), SIP 1042-1022#, FP 49-88 / 96-127#, HP 1972-2011#, BHT 105°
DST (4) 3722-3763 (ARB) / 25-20-0-0, REC 75' SLI OCM, ISIP 1003#, IFP 49-88#, HP 1972-2001#, BHT 95°
MICT - CO, PF (ARB) 3751-3758, W / 2 SPF, AC 500 GAL (15% MCA), SWB FL (11% OIL) / 60", NON-COMMERCIAL, SET BP AT 3768, SQZ'D PFS W / CMT, CO CMT, PF (ARB) 3740-3748, W / 2 SPF, AC 250 GAL (15% MCA), SWB 12 BO / 60", SWB DWN, SO, SET 2 7/8 " TBG AT 3744, POP, P 20 BOPD, NW, 10/2/85

INFO RELEASED: 3/12/87 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1987
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS