

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22245-00-00  
Spot: NWNESW Sec/Twnshp/Rge: 4-9S-21W  
2310 feet from S Section Line, 3705 feet from E Section Line  
Lease Name: NAPUE Well #: 4  
County: GRAHAM Total Vertical Depth: 4020 feet

Operator License No.: 9090  
Op Name: CHARTER ENERGY, INC.  
Address: PO BOX 252  
GREAT BEND, KS 67530

PROD Size: 5.5 feet: 3865 550 SX CMT  
SURF Size: 8.625 feet: 306 225 SX CMT

~~130~~ 130<sup>65</sup>

Well Type: SWD UIC Docket No: D24480.0 Date/Time to Plug: 04/13/2005 3:30 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: STEVE BAIZE Company: CHARTER ENERGY, INC. Phone: (785) 623-1861

Proposed Plugging Method: Ordered out 300 sxs Swift Multi-Density Cement and 1000# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/13/2005 5:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Swaged onto 5 1/2" - mixed and pumped 280 sxs SMD cement with 1000# hulls.  
Shut in. Cement 15' from surface.

Perfs:

Top	Bot	Thru	Comments
3803	4020		

RECEIVED  
APR 18 2005  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

*HD*

Signed

*Jay Pfeifer*  
(TECHNICIAN)

INVOICED


DATE 4-18-05

INV. NO. 2005061423

APR 14 2005

BROUGHER OIL, INC. #4 NAPUE 4-9-21W  
 P.O. DRAWER 1367 GREAT BEND, KS. 67530 NW NE SW  
 CONTR MOHAWK DRILLING CITY GRAHAM

GEOL BRENT REINHARDT FIELD MOREI



ELV 2217 KB SPD 10/3/85 CARD ISSUED 12/26/85 IP SWDW  
 2207 GL DRLG COMP 10/10/85 ARB OH 3865-4020

LOG	Tops	Depth/Datum	API 15-065-22,245
ANH	1685+	532	8 5/8 " 306 / 225SX, 5 1/2 " 3865 / 525SX
B/ANH	1715+	502	NO CORES OR DST'S
HOW	3115-	898	MICT - CO, PF (CHER) 3768-3776, W / 2 SPF, AC 5000G, SWB
TOP	3161-	944	DWN, NS, PF (FT SC) 3716-3720, W / 2 SPF, AC 250G, SWB
OREAD	3317-	1100	DWN, NSO, PF (MARM) 3666-3670, W / 2 SPF, AC 250G, SWB
PLATTSM	3340-	1123	LD, NS, RE-AC 500G, SWB DWN, NS, PF (LKC) 3585-3590, W / 2
HEEB	3374-	1157	SPF, AC 250G, SWB DWN, NS, SET 2 3/8 " TBG AT 3820', CON-
TOR	3398-	1181	VERTED TO SWDW, CO TO TD (ARB OH), SWDW - INJECTION
LANS	3416-	1199	RATE SATISFACTORY, 11/7/85
BKC	3629-	1412	
MARM	3649-	1432	
FT SC	3714-	1497	
CHER	3729-	1512	
ARB	3803-	1586	
RTD&LTD	4020-	1803	

COPYRIGHT 1985  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS