

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-179-20761-00-01  
Spot: CNWNWSW Sec/Twnshp/Rge: 26-6S-26W  
2600 feet from S Section Line, 4970 feet from E Section Line  
Lease/Unit Name: BRANDT FARMS Well Number: 1-26  
County: SHERIDAN Total Vertical Depth: 4352 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 378 w/225 sxs cmt  
Production: Size 5.5 feet: 4310 w/550 sxs cmt  
Liner: Size \_\_\_\_\_ feet:

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/01/2002 10:00 AM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: According to KCC Rules and Regulations.  
Ordered 250 sxs cement - 15 sxs gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/01/2002 11:00 AM

KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 378' w/225 sxs cement. 5 1/2" casing at 4310' w/550 sxs cement.  
Tied to 5 1/2" casing - spotted 40 sxs cement - 300# hulls - 15 sxs gel w/200# hulls.  
Squeezed 5 1/2" casing with 160 sxs cement.  
Max. P.S.I. 1000#. S.I.P. 950#.  
Tied to 8 5/8" x 5 1/2" annulus. Max. P.S.I. 500# (took no cement).  
Total of 200 sxs 60/40 pozmix - 10% gel - 15 sxs gel - 500# hulls.

RECEIVED  
OCT 17 2002  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY, PFEIFER WELL SERVICE-WATER.

Plugged through: CSG

District: 04

Signed

Roger L. Moses  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 10-18-02

INV. NO. 2003060656

OCT 15 2002


BEACON EXPLORATION  
 410-17TH ST. #2300  
 DENVER, CO 80202

REPLACEMENT CARD  
 #1-26 BRANDT FARMS  
 26-6-26W  
 NW NW SW

CONTR MURFIN DRILLING CO. CTY SHERIDAN

GEOL \_\_\_\_\_ FIELD WC(LUCERINE SE DISC)

ELV 2642 K.R. SPD 8/28/84 CARD ISSUED 11/1/84 IP P 110 BOPD, NW  
 2637 CL LKC 3800-3934 OA  
 API 15-179-20,761



SMP	Tops	Depth/Datum	OLD INFO: OPERATOR SAME, WELL NAME SAME, SPD 8/28/84, SET 8 5/8 " 378/225SX, 5 1/2 " 4310/550SX COMP AS P 218 BOPD, NW, LKC J 3929-3934
ANH	.....	2256+ 386	DST (1) 3780-3818 (LKC) / TIMES NA, 216' GIP, REC 163' MDY OIL, (30% M), 1890' OIL (5% M), SIP 990-990#, FP 256-256 / 361-723#, HP 1871-1871#
BY ANH	.....	2289+ 353	
TARK LM	.....	3412- 770	DST (2) 3818-44 (LKC F) / TIMES NA, 650' GIP, REC 268' GSY OIL, 310' MDY WTRY GCO (25% M, 25% W, 15% G, 35% OIL), 124' OCMW (30% M, 65% W, 5% OIL), 310' MW, SIP 1238-1209#, FP 85-114 / 190-380#, HP 1938-1919#
TOP	.....	3572- 930	
HEEB	.....	3730-1088	DST (3) 3866-93 (LKC H) / TIMES NA, REC 20' OCM (5% OIL), SIP 1125-1333#, FP 77-77 / 77-77#, HP 1973-1951#
TOR LM	.....	3752-1110	
LANS	.....	3770-1128	ARB DOL ..... 4292-1650 LTD ..... 4350-1708 PBTD ..... 4036-1394 RTD ..... 4352-1710 INFO RELEASED: 3/14/85 - ADDED WELL INFO (over)
LANS B	.....	3800-1158	
LANS C	.....	3811-1169	
LANS F	.....	3841-1199	
LKC H	.....	3892-1250	
LKC J	.....	3929-1287	
LKC K	.....	3949-1306	
BKC	.....	3975-1333	
MARIM	.....	4090-1448	
CONG CHT	.....	4249-1607	

COPYRIGHT 1985  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS

BEACON EXPLORATION  
 410-17TH ST. #2300  
 DENVER, CO 80202

REPLACEMENT CARD  
 #1-26 BRANDT FARMS  
 26-6-26W  
 NW NW SW

DST (4) 3876-3932 (LKC J) / TIMES NA, REC 194' MDY OIL (50% OIL), 2646' CL GSY OIL (20% G), SIP 1286-1257#, FP 304-418 / 570-980#, HP 2005-1986#  
 MICT - CO, PF (LKC J) 3929-34, W/2 SPF, SWB DWN, VGSO, NAT, SET 2 7/8 " TBG AT 3947, POP, P 218 BOPD, NW (GR 35%) 9/14/84, (LKC C-H PAY REMAINS BEHIND PIPE)  
 NOTE: CORRECTION 9/13/84 - ORIGINALLY FIRST REPORTED IN C NW SW.  
 NEW INFO: OFF PMP, RE-WORKED 12/84, MICT -CO, PF (LKC C) 3811-38 & (LKC B) 3800-04, W / 2 SPF, SWB DWN, GSO, POP, P 110 BOPD, NW, 12/17/84

490104