

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-20147-00-01
Spot: NESESE , Sec/Twnshp/Rge: 36-6S-26W
990 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: LINDENMAN Well Number: VEJL 2
County: SHERIDAN Total Vertical Depth: 3875 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

Production Casing Size: 4.5 feet: 3874 100 SX CMT ^{125.94}
Surface Casing Size: feet: 0
Surface Casing Size: 7 feet: 287 140 SX CMT

Well Type: EOR UIC Docket No: E15006.1 Date/Time to Plug: 01/31/2003 5:00 PM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 240 sxs 60/40 pozmix - 10% gel - 500# hulls.
Perfs 3833' - 3839'. CIBP at 3771'. Junk in the hole.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/31/2003 8:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Tubing parted at 3250' - tied onto tubing and pumped 80 sxs cement with 300# hulls.
Pulled tubing to 1600' - pumped 75 sxs cement with 200# hulls.
Pulled tubing - tied onto casing with swedge and pumped 40 sxs cement.
Max. P.S.I. 800#. S.I.P. 100#.
Dug out backside and tied onto.
Backside pressured to 500# S.I.P.

Remarks: ALLIED CEMENTING COMPANY - TICKET #11349.

Plugged through: TBG

District: 04

Signed *Patrick Stacey*

(TECHNICIAN)

RECEIVED

FEB 19 2003

KCC WICHITA

INVOICED

DATE

2-19-03

INV. NO.

2003061214

Form CP-2/3

FEB 13 2003

OKMAR OIL COMPANY
WICHITA, KS.

#2 VEJL

36-6-26W
NE SE SE

Contr. PAINE DRUG CO.

Cty. SHERIDAN

Geol. MAX HOUSTON

Pool LINDEMAN WEST

E. 2566 KB Cm. 10/14/68 Cp. 12/31/68 IP PMP 50 BOPD, NW/
LANS 3833-39

API 15-179-20,147

SMP Tops	Depth	Datum	Csg.
			7" 287/140 SX 4" 3874
ANH	2154	+ 412	DST 3657-80/90", 90' OCM, 300'
TOP	3470	- 904	OCMW, BHP 1234-1189#, FP 35-
HEFB	3630	-1064	215#
TOR	3650	-1084	DST 3680-3702/1', 1525' CL GSY 0
LANS	3666	-1100	BHP 1198-1181#, FP 71-592#
BKC	3867	-1301	DST 3702-3722/1', 20' OIL&40'OCM
RTD	3875	-1309	160'W, BHP 1163-1137#, FP 26-
			134#
			DST 3722-43/1', 15' OCM, 840'W,
			BHP 1172-1154#, FP 35-465#
			DST 3765-3800/1', 480'W, BHP 1252
			-1216#/30", FP 26-259#
			DST 3828-48/1', 30'M, BHP 89-89#/ 30", FP 26-62#
			CO PF 24/3833-39, A 3000, REC LD
			SWB 96 BOPD, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS