

6-15-87

030886

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 179-20,554 -00-00

S/2 N/2 NW, SEC. 20, T 6 S, R 26 W/E

4290 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Lease Name Hardesty Well # 3

Operator: Kaiser Francis Oil Co.
Name & Address: Box 21468
Tulsa, Ok. 74121-1468

County Sheridan 128.86

Well Total Depth 3965' feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 384'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B. J. Titan License Number _____

Address Oakley, Kansas

Company to plug at: Hour: _____ PM Day: 15 Month: June Year: 19 87

Plugging proposal received from John Glenn

(company name) Kaiser Francis (phone) _____

were: 8 5/8" set at 384' w/250 sks cwc 4 1/2" set at 3961' w/150 sks.

Perfs 3625 - 3924. Order 200 sks thrifty mix 65/35 Poz 10% Gel 2% Dicol.

Cmt. Blend 350# Hulls. B. J. Titan Cmt. Co. LaRue Water Trucks.

L K Wireline Perforated 4 1/2" csg w/4 SPF at 1520' and 4 SPF at 2253.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:40 PM Day: 15 Month: June Year: 19 87

ACTUAL PLUGGING REPORT No pipe pulled. Squeeze down 4 1/2" csg. 100 sks cmt. blend w/350# Hulls. Max. Psi. 400# Close in 300# Psi. Squeeze down 8 5/8" - 4 1/2" annulus 100 Sk.

Cmt. Blend. Max. Psi. 300#. Close in 150#. Psi. Plug complete.

RECEIVED STATE CORPORATION COMMISSION

JUL 10 1987 7-10-87

CONSERVATION DIVISION Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (to be observed) observe this plugging.

DATE 7-13-87

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

INV. NO. 17476