

4-031879

10-16

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-21,065 ⁰⁶⁰⁰
90'S.ofC.
N2 SE SW /4 SEC. 17, 06 S, 26 W
900 feet from S section line
1980 feet from E section line

Operator license# 5663 Lease Ross Shipley well # 1

Operator: Hess Oil Company County Sheridan

Address: P.O. Box 1009 Well total depth 3950 feet ^{128.38}
McPherson, Kansas 67460 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 343 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Mallard JV, Inc. License# 4958

Address: McPherson, Kansas

Company to plug at: Hour: A.M. Day: 16 Month: October Year: 93

Plugging proposal received from: Bryan Hess

Company: Hess Oil Company Phone:

Were: Order 200 sxs. 60/40 pozmix - 6% gel - 3% cc.
Allied Cement Company.
Circulate and condition hole.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 12:20A.M., Day: 16, Month: October, Year: 93

Actual plugging report: Spot cement plugs with drill pipe.
1st. plug at 2250' w/25 sxs.
2nd. plug at 1375' w/100 sxs.
3rd. plug at 400' w/40 sxs.
4th. plug at 40' w/10 sxs.
15 sxs. rathole.
10 sxs. mousehole.

Remarks: Anhy. 2225' - 2258'
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: 2625 GL

I did observe the plugging.

Carl Goodrow

RECEIVED
STATE CORPORATION COMMISSION

INVOICED
DATE 12-10-93
INV. NO. 39461

(agent)
DEC 10 1993
12-10-93
Form CP-2/3
CONSERVATION DIVISION
Wichita, Kansas