

6 030884

15-179-05314-00-01
API NUMBER 15- 2-6-53

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SE SE NW, SEC. 20, T 6 S, R 26 (W/E)
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2970 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6586

Lease Name Hardesty Well # 1 INJ

Operator: Kaiser - Francis Oil Co.
Name & Address P.O. Box 21468
Tulsa, Oklahoma 74121-1468

County Sheridan 135.66

Well Total Depth 4174 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor B.J. Tittan License Number

Address Oakley, Kansas

Company to plug at: Hour: PM Day: 15 Month: 6 Year: 1987

Plugging proposal received from John Glenn

(company name) Kaiser - Francis (phone)

were: 8 5/8 set at 280 ' with 175 sx cuc. 5 1/2 set @ 4172 ' 150 sx.

Perf 3781 - 3913' order 200 sx thrifty mix 65/35 poz 10% gel 2% decel

cmt. blend. B.J. Tittan Cmt. Co. LaRue Water Trucks

L-K Wireline Perforated the 5 1/2 with 4 spf at 1520' and 4 S.P.F. at 2253'

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:40PM Day: 15 Month: 6 Year: 1987

ACTUAL PLUGGING REPORT No casing pulled - squeeze down 5 1/2" csg.

100 sx cmt blend max. PSI 300# close in 150# PSI

Squeeze down 8 5/8" - 5 1/2" annulus 100 sx cmt. blend

Max PSI 300# close in 150# psi plug complete.

RECEIVED
STATE CORPORATION COMMISSION

JUL 16 1987
07-16-87
CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 7-21-87

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

INV. NO. 17530