

15-79-05315-00-00

6-15-87

To: **6 030885**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 8-8-53
NW SE NW, SEC. 20, T 6 S, R 26 W/E
3630 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6568
Operator: Kaiser Francis Oil
Name & Address Box 21468
Tulsa, Ok. 74121-1468

Lease Name Hardesty Well # 2
County Sheridan 128.18
Well Total Depth 3944' feet
Conductor Pipe: Size 8 5/8" feet 343'
Surface Casing: Size 8 5/8" feet 343'

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor B. J. Titan License Number _____
Address Oakley, Kansas

Company to plug at: Hour: AM Day: 15 Month: June Year: 19 87

Plugging proposal received from John Glenn

(company name) Kaiser Francis (phone) _____

were: 8 5/8 set at 343' w/200 sks cwc 5 1/2 set at 3944' w/125 sks PBTD 3939'.

Perfs at 3767-3908. Order 200 sks Thrifty mix 65/35 Poz 10% Gel 2% Dical Cmt.

Blend 350# Hulls. B. J. Titan Cmt. Co. LaRue Water Trucks.

L K Wireline perforated 5 1/2" csg. w/4 SPF at 1520' and 4 SPF at 2253'

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 AM Day: 15 Month: June Year: 19 87

ACTUAL PLUGGING REPORT No casing pulled. Squeezed down 5 1/2" csg. 100 sks cmt. Blend

350# Hulls. Max. Psi. 300# close in 150# Psi. Squeeze down 8 5/8 - 5 1/2 annulus 100 sks

Cmt. Blend Max. Psi. 300# close in 150# Psi. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
7-10-87
JUL 10 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

(If applicable) observe this plugging.

INVOICED
DATE 7-13-87
INV. NO. 17475

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow