

4-041643 10-1-94

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-21,072 -0000

NW NW NW /4 SEC. 36, 06 S, 26 W
500 feet from N section line
600 feet from W section line

Operator license# 5663 Lease Shipley well # 1

Operator: Hess Oil Company County Sheridan

Address: P.O. Box 1009 Well total depth 3984 feet
McPherson, Kansas 67460 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 338 feet

129.48

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Mallard JV, Inc. License# 4958

Address: P.O. Box 1009, McPherson, Kansas 67460

Company to plug at: Hour: P.M. Day: 1 Month: October Year: 94

Plugging proposal received from: Carol

Company: Mallard JV, Inc. Phone: _____

Were: Order 190 sxs. 60/40 posmix - 6% gel and 1/4# floseal per. sx.
Spot all plugs through drill pipe with heavy mud between all plugs.

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 8:15P.M., Day: 1, Month: October, Year: 94

- Actual plugging report:
- 1st. plug at 2275' w/25 sxs.
 - 2nd. plug at 1440' w/100 sxs.
 - 3rd. plug at 390' w/40 sxs.
 - 4th. plug at 40' w/10 sxs.
 - 15 sxs. in rathole.
 - 10 sxs. in mousehole.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2643 GL

I did did not observe the plugging.

INVOICED

DATE 1-5-95
INV. NO. 41992

Dennis Hamel

(agent)
Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS
JAN 05 1995
1-5-95