

6 030974

10-7-87

API NUMBER 15-179-20,771 -00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE SE, SEC. 27, T 6 S, R 26 W/E

2310 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9123

Lease Name Brandt-Ficken Well # 1-27

Operator: Diamond Shamrock Exp Co.
Name & Address: Box 400
Amarillo, Texas 79188-0001

County Sheridan 130.98

Well Total Depth 4030 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 409

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton License Number _____

Address Oberlin, Kansas

Company to plug at: Hour: _____ PM Day: 7 Month: Oct. Year: 19 87

Plugging proposal received from Troy Cody

(company name) Diamond Shamrock (phone) _____

were: 8 5/8" set at 409' w/300 sks. 4 1/2" set at 4030' w/220 sks. Port Collar set at

2245' Anhy w/600 sks. Perf at 750' w/275 sks cwc. Perfa at 3800' - 3933'. Order 150 sks

Cement Blend 65/35 Poz 10% Gel 2% Dical 5 sks Hulls. Halliburton Cement Co. LaRue Water Trucks

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:40PM Day: 7 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT Squeeze 4 1/2" casing w/500# Hulls in with 150 sks. Cement Blend to Max
Psi 2000#. Close in Psi 1000#. Pressure 8 5/8" - 4 1/2" Annulus to 500#, Cement at surface.
Plug complete.

STATE CORP. COMMISSION

NOV 30 1987

11-30-87
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.)

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow

DATE 12-4-87

INV. NO. 19093

10-7