

6
030362

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-179-20, 783⁰⁰ R

NWNE SW SEC. 26, T. 6 S, R 26 WE

2310 feet from N/S section line

3630 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5342

Lease Name BRANDT FARMS Well # 2-26

Operator: BEACON EXPLORATION CO

County SHERIDAN 131.63

Name & Address 410 17th St. SBE 2300

Well Total Depth 4050 feet

DENVER, COLORADO

Conductor Pipe: Size _____ feet

80202

Surface Casing: Size 8 5/8 feet 378 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor MURFIN DRILLING CO. License Number 6033

Address 617 UNION CENTER WICHITA, KANSAS 67202

Company to plug at: Hour: AM Day: 17 Month: 12 Year: 19 84

Plugging proposal received from STEVE CARLTON

(company name) MURFIN DRILLING (phone) _____

were: ORDER 190 SX. 50/50 PZ 6 GEL. 3% + 2 SX. CELLOFLAKE - 1 8" PLUG.

SPOT WITH D.P. WITH HEAVY DRILL MUD BETWEEN PLUGS AND NO FLUID LOSS

RECEIVED
STATE CORPORATION COMMISSION 1-02-85

Plugging Proposal Received by JAN 02 1985 Carl Goodnow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Wichita, Kansas None X

Operations Completed: Hour: 11:30AM Day: 17 Month: 12 Year: 19 84

ACTUAL PLUGGING REPORT RAN D.P. TO 2275 BROKE CIRC. DISPLACED WITH 25SX.

CEMENT PULLED O.P. TO 1400 DISPLACED WITH 100SX. CEMENT PULLED

D.P. TO 380' DISPLACED WITH 40SX CEMENT PULLED O.P. SET PLUG

AND HULLS @ 40' WITH 10SX. TO BOTTOM OF CELLAR.

CIRCULATED 15 SX. CEMENT IN RATHOLE

HALLIBURTON CEMENT CO. ELEV. 2639 ANHY 2261-94 H TESTS LOG

Remarks: CLS 25 to 30,000
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did/did not) observe this plugging.

DATE 1-16-85

Signed Carl Goodnow
(TECHNICIAN)

INV. NO. 6490 12-17 18 1985

Dec 18 84
FORM CP-2/3
Rev. 01-84
6