

4-071006

9-18

249 R

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-179-21,049-00-00

SE SW NE /4 SEC. 23, 06 S, 26 W  
3240 feet from S section line  
1440 feet from E section line

Operator license# 30407

Lease Teel well # 1

Operator: Black Petroleum Company

County Sheridan

Address: Box 12922  
Wichita, Kansas 67277  
Thomas E. Black

Well total depth 3935 feet 127.88  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 317 feet

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: White & Ellis Drilling Rig #9 License# 5420

Address: Great Bend, Kansas 67530

Company to plug at: Hour: P.M. Day: 18 Month: September Year: 92

Plugging proposal received from: Judy Stuhlen

Company: White & Ellis Drilling Phone: 316-942-2741

Were: 8 5/8" 317' S.P. cwc. w/190 sx. 60/40 posmix - 2% gel. - 3% c.c.  
By Allied Cement. L.K.C. Well. Elv. 2608'. Anhy. 2193'. No circulation  
problems. Mud condition - 47 vis. - 9.0 weight - 9.2 water loss.  
Proposal 200 sx. 60/40 pozmix - 6% gel. - 1 sx. flocele. Circulate hole,  
spot with drill stem, heavy mud between all plugs.  
25 sx. @ 2210' - 100 sx. w/1 flocele @ 1400' - 40 sx. @ 360' - 10 sx.  
@ 40' - 15 sx. rathole (circulate).

Plugging Proposal Received by: By: Allied Cementing  
Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour: 11:30P.M., Day: 18, Month: September, Year: 92

Actual plugging report: Ordered 200 sx. 60/40 pozmix - 6% gel. -  
1 sx. flocele. Spot with drill stem, circulated hole, heavy mud between  
all plugs.

1st. plug @ 2210' w/25 sx. cement.  
2nd. plug @ 1400' w/100 sx. cement w/1 sx. flocele.  
3rd. plug @ 360' w/40 sx. cement.  
4th. plug @ 40' w/10 sx. cement.  
15 sx. in rathole (circulate) 10 sx. in mousehole (circulate)

Remarks: Cemented by: Allied Cementing.

Condition of casing(in hole): GOOD X BAD      Anhy. plug: YES X NO       
Bottom plug(in place): YES     , CALC     , NO      Dakota plug: YES X NO       
Plugged through TUBING X, CASING     . Elevation: 2608

I did[      ] / did not[ X ] observe the plugging.

DATE 10-13-92

INV. NO. 36430

RECEIVED  
STATE CORPORATION COMMISSION  
10-2-92  
OCT 2 1992  
CONSERVATION DIVISION  
Wichita, Kansas

*[Signature]*  
(agent)