

15-179-20237-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

NOV 6 1986

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME GLASGOW 'A'

WELL NUMBER 1

SPOT LOCATION NE NW SW

SEC. 21 TWP. 6 RGE. 26 (E) or (W)

COUNTY SHERIDAN

Date Well Completed 12-17-69

Plugging Commenced 10-28-86

Plugging Completed 10-28-86

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR A. L. ABERCROMBIE, INC.

ADDRESS 801 UNION CENTER, WICHITA, KS. 67202

PHONE # (316) 262-1841 OPERATORS LICENSE NO. 5393

Character of Well OIL
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? HAYS

Is ACO-1 filed? YES If not, is well log attached? YES

Producing formation LANSING KC Depth to top 3748 bottom 3949 T.D. 3978

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LANSING KC	OIL & WATER	3774	79	7"	355'	NONE
		3833	37	4 1/2"	3955'	NONE
		3904	07			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged 4 1/2' csg. with 4 sacks Hulls, 120 sacks cement with standing press of 150#

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor A. L. ABERCROMBIE, INC. License No. 5393
Address _____

Rt, #1, Box 56, Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

E. L. ABERCROMBIE (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

NOV 7 1986
11-7-86

(Signature) E L Abercrombie

(Address) RT 1 Box 56 Gt Bend Ks

SUBSCRIBED AND SWORN TO before me this 6th day of November, 1986

Sherrie L. Brooks
Notary Public

My Commission expires: August 21, 1990

Sherrie L. Brooks

15-179-20237-00-00

CONTRACTOR'S WELL LOG

OWNER: Abercrombie Drilling, Inc.
 OPERATOR: Abercrombie Drilling, Inc.
 WELL NAME: GLASGOW #1
 LOCATION: NE NW SW, Sec. 21-6S-26W
 Sheridan County, Kansas
 GEOLOGIST: Jack Wharton
 SPUD DATE: November 14, 1969
 COMPLETION DATE: November 23, 1969

0	295	Clay & Sand
295	1178	Shale
1178	1262	Sand
1262	1365	Shale
1365	1665	Shale & Sand
1665	1866	Shale
1866	2036	Sand
2036	2261	Shale
2261	2294	Anhydrite
2294	2555	Shale
2555	3295	Shale & Lime
3295	3675	Lime
3675	3750	Lime & Shale
3750	3930	Lime
3930	3978	Lime & Shale
	3978	Rotary Total Depth

Drilled 360' of 9" surface hole and set 7" csg. @355' w/100 sx. Sunset cement. Cement circulated. Plug was down at 11:15 p.m., 11-14-69.

Ran 4 1/2" O.D., 8-rd Thread, 9 1/2# new csg. and set @3955' w/35 sx. 50-50 posmix w/2% gel and 12# gilsonite per sx. and 60 sx. common cement w/2% gel, 10% salt, 1% c.c., and 2# friction reducer. Plug was down at 7:30 a.m., 11-23-69.

ELECTRIC LOG TOPS

ELEVATION

Anhydrite	2262	(+ 395)	2657	K. B.
Heebner	3706	(-1049)	2655	D. F.
Toronto	3728	(-1071)	2649	G. L.
Lansing	3744	(-1087)		
B/K.C.	3949	(-1292)		
E.L.T.D.	3978	(-1321)		
R.T.D.	3978	(-1321)		

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

NOV 7 1969
 11-7-86

Jerry A. Langrehr, president of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Glasgow #1, NE NW SW, Sec. 21-6S-26W, Sheridan County, Kansas, as reflected by its file.

Jerry A. Langrehr
 Jerry A. Langrehr

Subscribed and sworn to before me, a Notary Public, in and for the county and state above mentioned, as of this 24th day of November, 1969.

Sue J. Blunck
 Sue J. Blunck, Notary Public

My Commission Expires:

July 15, 1972