


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-179-05318-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Sheridan County. Sec. 21 Twp. 6 Rge. 21 (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NE NE NW
Lease Owner HARRY GORE
Lease Name GLASGOW Well No. 1
Office Address 400 Brown Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-4-51 19
Application for plugging filed 11-4-51 19
Application for plugging approved 11-4-51 19
Plugging commenced 11-4-51 19
Plugging completed 11-4-51 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Petty
Producing formation Depth to top Bottom Total Depth of Well 4315 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface	Pipe	0	192	8-5/8"	192	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug at 180' and cemented with 15 sacks of cement.
Set plug at 40', put in 1/2 sack of hulls on top of plug and cemented with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 15 1951

11-15-51

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor EMPIRE DRILLING COMPANY
Address 1121 Union National Bank Bldg., Wichita, Kansas.


STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dan J. Kornfeld (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan J. Kornfeld
1121 Union Nat'l. Bank Bldg., Wichita (Address)

SUBSCRIBED AND SWORN to before me this 7th day of November 19 51

Evelyn V. North
Notary Public.

My commission expires Dec. 22, 1954.



COMPANY: HARRY CORE
 CONTRACTOR: Empire Drilling Company
 FARM: Known as the GLASGOW NO. 1
 LOCATION: NE NE NW Sec. 21-4-26W Sheridan County, Kansas
 COMMENCED: 10-19-51
 COMPLETED: 11-4-51

0	to	38	Surface Clay
38	to	194	Sand, Clay & Shells
194	to	442	Sand, Shale & Shells
442	to	895	Shale & Shells
895	to	1410	Shale & Shells
1410	to	1565	Shale & Shells
1565	to	1640	Shale
1640	to	1660	Sand (Dakota)
1660	to	1725	Shale & Lims
1725	to	1855	Lims, Shales & Shells
1855	to	2285	Shale
2285	to	2310	Anhydrite
2310	to	2375	Shale & Lims streaks
2375	to	2765	Shale & Lims
2765	to	3005	" "
3005	to	3220	" "
3220	to	3375	" "
3375	to	3550	" "
3550	to	3835	Lims
3835	to	3991	Lims & Shales
3991	to	4037	Shale
4037	to	4223	"
4223	to	4255	Lims & Chert
4255	to	4262	Shale & Chert
4262	to	4264	Chert
4264	to	4309	Arbuckle
4309	to	4315	" P. D. Rotary

Set 192' 8-5/8" surface pipe. Cemented with 130 sacks cement.

Run Schlumberger Electric Log at 4315'.
 Tops: Heilner 3735', Toronto 3757', Lansing-K. G. 3773', Base K. G. 3970', Basal Penn. Cong. 4190', Weathered Viola 4243', Simpson 4254', Arbuckle 4264'.
 All measurements from top of rotary bushings.
 Elevation: 2645' D. F.

DRY.

CERTIFICATE

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log of the Glasgow No. 1 in Sec. 21-4-26W, Sheridan County, Kansas, as reflected by files of the Empire Drilling Company.

Dan J. Kornfeld
 Dan J. Kornfeld

Subscribed and sworn to before me, Notary Public, within and for Sedgwick County, Kansas, this 7th day of November, 1951.

Evelyn V. North
 Evelyn V. North
 Notary Public

RECEIVED

STATE CORPORATION COMMISSION

My commission expires Dec. 22, 1951.

NOV 15 1951 sec 21-6-26W

CONSERVATION DIVISION
 Wichita, Kansas

11-15-51