

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

15-179-20495-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Sheridan SEC. 20 TWP. 6S RGE. 26W E/W
 Location as in quarters or footage from lines:
440' FNL 440' FWL of NE/4

Lease Owner A. Scott Ritchie
 Lease Name Glasgow #1 Well No. _____
 Office Address Suite 950 125 N. Market Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 5-6-82
 Plugging completed 5-11-82
 Reason for abandonment of well or producing formation _____
Depelted

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow
 Producing formation _____ Depth to top _____ bottom _____ T.D. 1271'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	352'	none
				4-1/2"	3963'	1271'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Pushed bottom plug to 3800', ran 25' of sand and 4 sacks cement. Shot casing @3370',
 3248', 3110', 2983', 2857', 2730', 2417', 2204', 1997', 1607', 1414', 1278'. Pulled a
 total of 29 joints of 4-1/2" casing. Plugged well with 2 hulls, 20 gel, 1 hulls,
 70 cement, 1 hulls, 20 gel, released plug and displaced with 70 sacsk cement.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

MAY 24 1982


R. Darrell Kelso (Signature)

CONSERVATION DIVISION
 Wichita, Kansas

Box 176 Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of May, 19 82

My Commission expires: _____



Irene Hoover
 Notary Public.