


15-179-00069-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sheridan County. Sec. 26 Twp. 6 Rge. (E) 26 (W)
Location as "NE/CNW&SW&" or footage from lines NE NE NE
Lease Owner Empire Drlg. Co. and Time Petroleum Co.
Lease Name R. U. Wente Well No. 1
Office Address 650 Fourth National Bank Building
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 18, 1958 19
Application for plugging filed November 18, 1958 19
Application for plugging approved November 18, 1958 (Verbally) 19
Plugging commenced November 18, 1958 19
Plugging completed November 18, 1958 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3945 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	298	8 5/8"	298	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug set @ 600' with 20 sacks cement
Second Plug set @ 290' with 20 sacks cement
Top plug set @ 40' with 10 sacks cement to ground level.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Empire Drilling Company
Address 650 Fourth National Bank Building

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, Dan J. Kornfeld (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
650 Fourth National Bank Building
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of November, 19 58
[Signature]
My commission expires October 21, 1962 Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
NOV 25 1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 26 T. 6 R. 26W
BOOK PAGE 146 LINE 38

L O G

COMPANY: Empire Drilling Company, Wichita, Kansas
 Time Petroleum Company, Wichita, Kansas

CONTRACTOR: Empire Drilling Company, Wichita, Kansas

FARM: R. U. Wente No. 1

LOCATION: NE NE NE Section 26-6-26W, Sheridan County, Kansas

COMMENCED: November 10, 1958 ELEVATION: 2615 KB
 COMPLETED: November 18, 1958 POTENTIAL: D & A

0	to	312	Sand and Shale
312	to	2195	Shale and Shells
2195	to	2238	Anhydrite
2238	to	3025	Shale and Shells
3025	to	3250	Shale and Lime
3250	to	3340	Lime and Shale
3340	to	3425	Shale and Lime
3425	to	3570	Lime and Shale
3570	to	3675	Shale and Lime
3675	to	3945	Lime
		3945	RTD

SET: 8 5/8" 298' with 200 Sacks Cement

TOPS: Heebner 3688
 Toronto 3712
 Lansing Kansas City 3729
 Base Kansas City 3930

C E R T I F I C A T I O N

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the R. U. Wente No. 1, NE NE NE Section 26-6-26W, Sheridan County, Kansas, as reflected by the files of the Empire Drilling Company.

Dan J. Kornfeld
 Dan J. Kornfeld

Subscribed and sworn to before me, a notary public within and for Sedgwick County, Kansas this 21st Day of November, 1958

Charlotte Stanley
 NOTARY PUBLIC

My Commission expires June 7, 1960

STATE CORPORATION
 NOV 25 1958
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC. 26 T. 6 R. 26W
 BOOK PAGE 146 LINE 38