

15-179-20043-00-00

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Sheridan SEC. 23 TWP. 6 RGE. 26W E/W  
 Location as in quarters or footage from lines:  
200' E of SE NW


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner A.L. Abercrombie, Inc.  
 Lease Name Brandt #1 Well No. \_\_\_\_\_  
 Office Address 801 Union Center Wichita, Ks. 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 8-31-82  
 Plugging completed 9-8-82  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted  
 Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3855'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				7"	294'	none
				4-1/2"	3854 1/2'	1005'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged off bottom with sand to 3300' and ran 4 sacks cement. Shot casing @3218' 2527', 2340', 2006', 1729', 1523', 1402', 1316', 1210', 1128', 1014' and pulled a total of 32 joints of 4-1/2" casing. Plugged well with 4 sacks hulls, 25 sacks gel, 70 sacks cement, 15 sacks gel, 60 sacks cement, released plug and displaced with 10 sacks cement.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347 Chase, Ks. 67524  
 (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of September, 19 82

Irene Hoover  
 Notary Public



My Commission expires:

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 14 1982  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 9-14-82