

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-065-20,883-00-00 (of this well) 6/88
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR DYCO PETROLEUM CORPORATION OPERATORS LICENSE NO. 8461
ADDRESS 7130 South Lewis, Suite 300, Tulsa, Oklahoma 74136 PHONE # (918) 496-7600
LEASE (FARM) Walters WELL NO. 1 WELL LOCATION SW/4 COUNTY Graham
SEC. 32 TWP. 6S RGE. 23W or (W) TOTAL DEPTH 3,982' PLUG BACK TD 3,982'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____
SURFACE CASING SIZE 8 5/8" SET AT 315 CEMENTED WITH 200 SACKS
CASING SIZE 4 1/2" SET AT 3,982 CEMENTED WITH 200 SACKS
PERFORATED AT 3,798'-3,802', 3,868'-3,872', 3,706'-3,710', 3,916'-3,919', 3,422'-3,426'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1) Set GIBP W 3,400', cap w/cement
2) 50 sk. cmt plug at casing stub 3) 20 sk. cmt plug at 315' 4) 10 sk. cmt plug at 33'-3',
hole to be full of 9.0 PPG Mud

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES IS ACO-1 FILED?
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
David Kvach - Garrison Engineering PHONE # (918) 492-8400

ADDRESS 2626 E. 72nd St., Tulsa, Oklahoma 74136

PLUGGING CONTRACTOR Not Selected LICENSE NO. _____

ADDRESS _____ PHONE # () _____

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: [Signature]
(Operator or Agent)

DATE: September 1, 1987

4

RECEIVED
STATE CORPORATION COMMISSION
SEP 3 1987
1907



Mike Hayden	Governor
Keith R. Henley	Chairman
Rich Kowalewski	Commissioner
Margalee Wright	Commissioner
Judith A. McConnell	Executive Director

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 200 Colorado Derby Building
 202 West 1st Street
 WICHITA, KANSAS 67202-1286

THIS NOTICE

DEC 3 '87

EXPIRES

September 3, 1987

WELL PLUGGING NOTICE

Walters #1
 SW/4
 Sec. 32-06S-23W
 Graham County

Dyco Petroleum Corporation
 7130 S. Lewis, Ste. 300
 Tulsa, OK 74136

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

 Shari Feist
 Director
 State Corporation Commission