

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-27631-00-01
Spot: NENWNWSE Sec/Twnshp/Rge: 3-26S-18E
2475 feet from S Section Line, 2140 feet from E Section Line
Lease Name: FINNEY NORTH Well #: 72
County: ALLEN Total Vertical Depth: 847 feet

Operator License No.: 32902
Op Name: HOPEWELL OPERATING, INC.
Address: 4600 GREENVELLE AVE., SUITE 200
DALLAS, TX 75206

PROD Size: 2.875 feet: 847
SURF Size: 6.25 feet: 20

A 35⁰⁰

Well Type: EOR UIC Docket No: E24521.1 Date/Time to Plug: 04/02/2005 9:45 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY
Proposal Rcvd. from: MIKE WIMSETT Company: W & W PRODUCTION COMPANY Phone: (620) 431-4137

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CASING TO 847' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE
Date/Time Plugging Completed: 04/02/2005 10:10 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 580PSI. 38 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

Top	Bot	Thru	Comments
799	847	CSG	SURFACE

RECEIVED
APR 11 2005
KCC WICHITA

RECEIVED
KCC DISTRICT #3
APR 6 2005 CPT
CHANUTE, KS

Remarks:

Plugged through: CSG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

INVOICED
DATE 4-12-05
INV. NO. 2005D61398