

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03171-00-01⁰³
Spot: SESESW Sec/Twnshp/Rge: 21-10S-23W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: DIEBOLT Well #: 8-1
County: GRAHAM Total Vertical Depth: 3885 feet

Operator License No.: 33069
Op Name: ENCORE OPERATING COMPANY
Address: P. O. BOX 27710
DENVER, CO 80227

PROD Size: 5.5 feet: 3883 175 sx
SURF Size: 10.75 feet: 235 175 sx

#126²⁶

Well Type: EOR UIC Docket No: E09110.3 Date/Time to Plug: 04/04/2005 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: ROLAND NYP Company: ENCORE OPERATING COMPANY Phone: (785) 737-3242

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 10% gel - 800# hulls.
Casing leak 1560'-1592' - squeezed with 150 sxs in 1953.
Holes in casing. Well had anguard in it. Was not reported on MIT.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/04/2005 12:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 2100'.
Rigged to tubing and pumped 285 sxs with 500# hulls mixed in to circulate cement to surface.
Pulled tubing - rigged to 5 1/2" casing with a swedge.
Pumped 50 sxs cement with 100# hulls mixed in.
Max. P.S.I. 600#. S.I.P. 500#.
Rigged to 10 3/4" casing and pumped 65 sxs cement.
Max. P.S.I. 200#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3716	3841	OH	

RECEIVED
APR 08 2005
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS TREXLER A-1. ALLIED CEMENTING COMPANY-TICKET #19195.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

INVOICED
DATE 4-8-05
NO. 2005061392

Form CP-2/3

APR 05 2005

