

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-001-27515-00-00  
Spot: Sec/Twnshp/Rge: 3-26S-18E  
2475 feet from S Section Line, 1485 feet from E Section Line  
Lease Name: N FINNEY Well #: 74  
County: ALLEN Total Vertical Depth: 1000 feet

Operator License No.: 32902  
Op Name: HOPEWELL OPERATING, INC.  
Address: 4600 GREENVILLE AVE., SUITE 200  
DALLAS, TX 75206

PROD Size: 2.875 feet: 1000  
SURF Size: 7 feet: 20

#35<sup>00</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/02/2005 9:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY  
Proposal Rcvd. from: \_\_\_\_\_ Company: W & W PRODUCTION COMPANY Phone: (620) 431-4137

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 1000' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE  
Date/Time Plugging Completed: 04/02/2005 9:30 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 750PSI.

RECEIVED  
KCC DISTRICT #3

APR 6 2005

CHANUTE, KS

CPT

RECEIVED  
APR 11 2005  
KCC WICHITA

Remarks:

Plugged through: CSG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

INVOICE

DATE

4-12-05

INV. NO.

2005061398