

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-21300-00-01  
Spot: SENESW Sec/Twnshp/Rge: 7-18S-9W  
1550 feet from S Section Line, 3160 feet from E Section Line  
Lease Name: KINEMOND Well #: 1  
County: RICE Total Vertical Depth: 3227 feet

Operator License No.: 31528  
Op Name: KELSO, MIKE - OIL, INC.  
Address: PO BOX 467  
CHASE, KS 67524

PROD Size: 4.5 feet: 3215 150 SX CMT  
SURF Size: 8.625 feet: 257 165 SX CMT

# 104<sup>88</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/16/2005 3:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE  
Date/Time Plugging Completed: 03/16/2005 5:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded open hole to 3150' and put 4 sacks of cement on top. Cut off casing at 1503'. Pulled casing to 1200' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 850' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 310' and circulated cement to surface.

Allied Cement #20725

60/40 posmix with 4% gel

Perfs:

RECEIVED  
KCC DISTRICT #2  
MAR 30 2005  
WICHITA, KS

RECEIVED  
APR 11 2005  
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

INVOICED

DATE

4-12-05

BY

2005061400