

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-06378-00-00
Spot: NWSESW Sec/Twnshp/Rge: 7-18S-9W
990 feet from S Section Line, 3630 feet from E Section Line
Lease Name: BREDFELDT Well #: 2
County: RICE Total Vertical Depth: 3235 feet

Operator License No.: 31528
Op Name: KELSO, MIKE - OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

CIBP Size: feet: 2710
PROD Size: 5.5 feet: 3206 115 SX CMT
SURF Size: 8.625 feet: 195 100 SX CMT

105¹⁴

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/17/2005 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Sand perforations to 2630' and put 5 sacks of cement on top; cut off casing and pull to 1200' and pump 35 sacks of cement; Plugging pull to 850' and pump 35 sacks of cement; pull casing to 250'; and circulate cement to surface. Method:

Plugging Proposal Received By: _____ WitnessType: PARTIAL
Date/Time Plugging Completed: 03/17/2005 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2610' and put 5 sacks of cement on top. Cut off casing at 1526'. Pulled to 1200' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled to 850' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 250' and circulated cement to surface.

Allied Cement #20654

60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
3052	3058		
3036	3040		
2964	2968		
2942	2952		
2682	2686		

RECEIVED
APR 11 2005
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED

DATE 4-12-05
INV. NO. 2005061400