

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25402-00-00  
Spot: NWNENE Sec/Twnshp/Rge: 7-13S-20W  
450 feet from N Section Line, 1000 feet from E Section Line  
Lease Name: BITTLE Well #: 1  
County: ELLIS Total Vertical Depth: 3855 feet

Operator License No.: 6861  
Op Name: RON'S OIL OPERATIONS INC  
Address: RFD 1, 1889 200 AVENUE  
PENOKEE, KS 67659

SURF Size: 8.625 feet: 220

\$12500

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/08/2005 6:00 AM  
Plug Co. License No.: 33237 Plug Co. Name: ANDERSON, C. D. DBA ANDERSON DRILLING  
Proposal Rcvd. from: DARREL ANDERSON Company: ANDERSON, C. D. DBA ANDERSON Phone: (785) 421-2234

Proposed Plugging Method: Order 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES  
Date/Time Plugging Completed: 04/08/2005 8:45 AM

Witness Type: NONE  
KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3840' w/25 sxs.  
2nd. Plug at 1550' w/25 sxs.  
3rd. Plug at 875' w/100 sxs.  
4th. Plug at 275' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.

Perfs:

RECEIVED  
APR 11 2005  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



INVOICED (TECHNICIAN)

DATE 4-12-05  
INV. NO. 2005061402

Form CP-2/3

APR 08 2005