

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 179-20, 716 00-00

SE-NW-SW, Sec. 21, T 6 S, R 26 WE  
1650 feet from N/S section line  
1650990 feet from WE section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 8420

Lease Name MAUCK Well # 1  
County SHERIDAN

Operator: S. + K. ENTERPRISES  
Name & Address BOX 544  
HOXIE, KS.  
67740

Well Total Depth 4000 feet \$ 130.00  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 288

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor BIG SPRINGS DRILLING License Number 5381

Address BOX 8287 WICHITA, MO. 67208

Company to plug at: Hour: 2:15 AM Day: 6<sup>th</sup> Month: DEC Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO STEVE BASIE

(company name) BIG SPRINGS DRILLING (phone) 913-675-2396

were:  
8 5/8" - 288' S.B. CUL #180<sup>SK</sup> COMMON - 2% GEL - 3% CA-CL. (BY ALLIED CMT.)  
ORDER 195<sup>SK</sup> 50/50 FORMIX 6% GEL - 3% CA-CL. - 1<sup>SK</sup> CELLO FINNE AND 8 5/8' DRUG  
SPOT WITH DRILL STEM - TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS.  
NO ARBUCKLE, ELV. 2653, ANH. 2265'

Signed Martin Schmidt  
(TECHNICIAN) BOIC

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 2:15 AM Day: 6<sup>th</sup> Month: DEC Year: 19 83

ACTUAL PLUGGING REPORT  
ORDERED 195<sup>SK</sup> 50/50 FORMIX 6% GEL - 3% CA-CL., 1<sup>SK</sup> CELLO FINNE AND 8 5/8" DRUG  
SPOTTED WITH DRILL STEM - TURNED HOLE OVER - HEAVY MUD BETWEEN PLUGS  
1<sup>st</sup> Plug @ 2280 FT #25<sup>SK</sup> CNT, 2<sup>nd</sup> Plug @ 1350 FT #100 CNT #1<sup>SK</sup> CELLO FINNE  
3<sup>rd</sup> Plug @ 300 FT #50<sup>SK</sup> CNT, 4<sup>th</sup> Plug SOLID BRIDGE HULLS-DRUG @ 40 FT #10 CNT.  
10<sup>SK</sup> RAT HOLE (CIRCULATE) CEMENTED BY ALLIED CMT.

Remarks: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED RECEIVED  
STATE CORPORATION COMMISSION

Signed Martin Schmidt  
(TECHNICIAN) BOIC

DATE 1-11-84 DEC 12 1983

FORM CP-2/3  
5 Rev. 9-82

INV. NO. 8196 W  
CONSERVATION DIVISION  
Wichita, Kansas