

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20982-00-00
Spot: CSESESE Sec/Twnshp/Rge: 19-6S-25W
330 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: KLEIN 1 Well Number: A
County: GRAHAM Total Vertical Depth: 3900 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 340 w/200 sxs cmt
Production: Size 4.5 feet: 3899 w/100 sxs cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/27/2002 8:00 AM
Plug Co. License No.: 32579 Plug Co. Name: PFEIFER DOZER SERVICE, LLC
Proposal Rcvd. from: DISTRICT #4 STAFF Company: PFEIFER DOZER SERVICE, LLC Phone: (785) 627-5711

Proposed Plugging Method: Ordered 325 sxs 60/04 pozmix - 10% gel plus hulls.
Perf casing at 1325' and 2250'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/27/2002 1:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:
Perf casing at 1325' - 2250'.
R.I.H. with tubing to 2300'.
Pumped 225 sxs cement with 400# hulls in cement to circulate at surface.
POOH with tubing and squeezed casing with 25 sxs cement.
Max. P.S.I. 600#. S.I.P. 500#.
R.U. Cementers to 8 5/8" S.P. Squeezed 50 sxs cement with 100# hulls.
Max. P.S.I. 600#.

RECEIVED
JUL 05 2002
KCC WICHITA

Remarks: SWIFT SERVICES, INC.
Plugged through: TBG

District: 04

Signed Dennis J. Hamel
(TECHNICIAN)

(Handwritten mark)

JUL 30 2002

NATIONAL OIL CO.
200 W. DOUGLAS, SUITE 550
WICHITA, KS.

#1 KLEIN

19-6-25W
SE SE SE

CONTR JOHN O. FARMER, INC.

CTY GRAHAM

GEOL JAY DIRKS

FIELD WC (1/2 E OF ALLODIUM; SEP BY DRY HOLES)

E 2600 KB CM 1/28/78 CARD ISSUED 5/11/78 IP STATE POT P 32 BOPD

API 15-065-20,982

NW
LKC 3831-61 OA

+	+	+
+	+	+
-	+	+

LOG	TOPS	DEPTH	DATUM
HEEB		3644	-1044
TOR		3668	-1068
LANS		3684	-1084
BKC		3873	-1273
RTD		3900	-1300
LTD		3900	-1300

8-5/8" 340/200sx, 4 1/2" 3899/100sx
DST (1) 3711-25/30-30-30-30, 30' M W/
SSO, SIP 1201-1170#, FP 76-76#
98-98#
DST (2) 3731-58/30-30-30-30, 40' SOCM
SIP 370-63#, FP 21-21#, 21-21#
DST (3) 3810-38/30-30-60-60, 744' G.I.P
1178' CL GSY 0, 124' MCO, 62' VHOCM
(GVTY 36°), SIP 1233-1222#, FP
131-283#, 349-544#
MICT - CO, PF (LKC) 10/3831-36, 6/3858-
61, AC 1000, SWB DWN & COMM W/ANNULUS,
AC 500 (3858-61) COMM W/UPPER PFS, AC
1000, SWB GSO OFF BTM, ONFU 2500' 0,
NW, SWB DWN & REC 31.6 BO, NW, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS