

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22350-00-00
Spot: NWSESESE Sec/Twnshp/Rge: 19-6S-25W
600 feet from S Section Line, 600 feet from E Section Line
Lease/Unit Name: KLEIN 1 Well Number: B
County: GRAHAM Total Vertical Depth: 3900 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 296
Production: Size 5.5 feet: 3896
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/25/2002 9:00 AM

Plug Co. License No.: 32579 Plug Co. Name: PFEIFER DOZER SERVICE, LLC

Proposal Rcvd. from: DISTRICT #4 STAFF Company: PFEIFER DOZER SERVICE, LLC Phone: (785) 627-5711

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 10% gel - 600# hulls.
Perf casing at 1325' - 2250'.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 06/25/2002 2:00 PM

KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Perf casing at 1325' and 2250'.
R.I.H. with tubing to 2300'.
Pumped 225 sxs 60/40 pozmix - 10% gel with 500# hulls in cement to circulate cement at surface.
POOH with tubing and squeezed casing with 40 sxs cement.
Max. P.S.I. 500#. S.I.P. 300#.
R.U. Cementers to 8 5/8" S.P. Squeezed 35 sxs cement down S.P.
Max. P.S.I. 600#.

RECEIVED
AUG 05 2002
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

Dennis J. Hamel

(TECHNICIAN)

replacement card

WILLIAMSON DRILLING
GREAT BEND KS 67530

19-06S-25W
600' FSL & 600' FEL, SEC

#1 KLEIN

site: 10-3/4 N & 3-3/4 W OF MORLAND KS	city: GRAHAM	API 15-065-22350
contr: WILLIAMSON DRILLING	field: ALLODIUM EAST	
geol:		
fr date 01/06/1987	spd date 01/13/1987	drig comp 01/20/1987
	card issued 02/03/1988	last revised 08/07/2000

ELV: 2597 KB
 topsdepth/datum
 RTD3900 -1303
 NO TOPS RPTD

IP status:
D&A, LKC , 06/01/1987
 INFO RELEASED: 8/7/2000 - WAS TEMP ABD
 CSG: 8-5/8" 296, 5-1/2" 3896
 NO CORES
 DST (1) 3807-3845 (LKC), MISRUN
 DST (2) 3807-3845 (LKC), / TIMES NA, REC 40' V SLI OCM, PRESSURES NA
 DST (3) 3693-3763 (LKC, W/STR PKR), MISRUN
 DST (4) 3693-3763 (LKC, W/STR PKR), / TIMES NA, REC 30' OIL, 120' OCM, 120' HOCM, PRESSURES NA
 MICT - CO, PF (LKC) INTV NA, AC'D, NON-COMMERCIAL,
 SI - EVAL (6/1/1987); WELL NEVER PRODUCED; NO FURTHER ACTIVITY RPTD; CHGD STATUS TO D & A (DATE NA) - NO OTHER INFO AVAILABLE