

6 031400

0000248
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-22,572

NE SW SE, SEC. 30, T 6 S, R 23 W7E

990 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Sunday Well # 1

Operator: Ritchie Exploration Inc.

County Graham 127.40

Name & Address 125 N. Market Suite 1000

Well Total Depth 3920 feet

Wichita, Ks. 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 295

Abandoned Oil Well Gas Well Input Well SWD Well D&A xx

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling License Number 6033

Address Wichita, Ks.

Company to plug at: Hour: AM Day: 12 Month: June Year: 19 90
Lloyd Dellette

Plugging proposal received from

(company name) Murfin (phone)

were: 8 5/8 set at 295 w/180 sks. Circ hole w/no less than 36 vis mud w/no loss or gain in fluid. Balance plugs w/mud. Order 190 sks. 60/40 poz 6% gel 3% cc. 8 5/8 w.p. Allied Cement Co. Water well plugged by Woofter.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None xx

Operations Completed: Hour: 11:30AM Day: 12 Month: June Year: 19 90

ACTUAL PLUGGING REPORT Spot cement plugs w/drill pipe at 2150 w/25 sks

1250 w/100 sks and hulls RECEIVED
300 w/40 sks 8-7-90 COMMISSION
40 w/10 sks w.p. 8-7-1990

Circ 15 sks in rathole w/joint pipe.

Remarks: Elev. 2443 Anhy 2140 - 72 (If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 15 1990

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow

INV. NO. 28934